

INDEX OF SHEETS

1	TITLE SHEET
2	INDEX OF SHEETS, IDOT STANDARDS AND GENERAL NOTES
3 - 4	SUMMARY OF QUANTITIES
5	TYPICAL SECTIONS
6	ALIGNMENT, CONTROL POINTS AND BENCHMARKS
7	EXISTING AND REMOVAL PLAN
8	ROADWAY PLAN & PROFILE
9	MAINTENANCE OF TRAFFIC TYPICALS
10 - 11	MAINTENANCE OF TRAFFIC
12	GENERAL PLAN & ELEVATION
13	GENERAL NOTES, INDEX & QUANTITIES
14	TYPICAL CROSS SECTION & STAGING
15	17" x 36" PCC DECK BEAM
16	17" x 36" PCC BEAM DETAILS
17	PARAPET DETAILS
18 - 19	BIKEWAY RAILING DETAILS
20	TEMPORARY BARRIER DETAILS
21	SOUTH ABUTMENT DETAILS
22	NORTH ABUTMENT DETAILS
23	ABUTMENT DETAILS
24 - 26	APPROACH SLAB DETAILS
27 - 36	DETAILS

LIST OF STANDARDS

<u>NUMBER</u>	<u>STATE STANDARD</u>
000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
280001-05	TEMPORARY EROSION CONTROL SYSTEMS
420401-08	BRIDGE APPROACH PAVEMENT CONNECTOR
515001-03	NAME PLATES FOR BRIDGES
606001-04	CONCRETE CURB TYPE B AND COMBINATION CURB AND GUTTER
630001-09	STEEL PLATE BEAM GUARDRAIL
631011-07	TRAFFIC BARRIER TERMINAL, TYPE 2
631026-05	TRAFFIC BARRIER TERMINAL, TYPE 5
631031-09	TRAFFIC BARRIER TERMINAL, TYPE 6
635001-01	DELINEATORS
635006-03	REFLECTOR AND TERMINAL MARKER PLACEMENT
635011-02	REFLECTOR MARKER AND MOUNTING DETAILS
701101-02	OFF-ROAD OPERATIONS, MULTILANE, 15' (4.5M) TO 24' (600MM) FROM PAVEMENT EDGE
701801-04	LANE CLOSURE, MULTILANE 1W OR 2W, CROSSWALK OR SIDEWALK CLOSURE
701901-01	TRAFFIC CONTROL DEVICES
704001-06	TEMPORARY CONCRETE BARRIER
780001-02	TYPICAL PAVEMENT MARKINGS
781001-03	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS
<u>DISTRICT 1 STANDARDS</u>	
BD-32	BUTT JOINTS AND HMA TAPER
TC-11	RAISED REFLECTOR PAVEMENT MARKERS (SNOW PLOW RESISTANT)
TC-22	ARTERIAL ROAD INFORMATION SIGN

GENERAL NOTES

- ALL CONSTRUCTION SHALL BE IN CONFORMANCE WITH THE APPLICABLE REQUIREMENT SET FORTH IN "THE CONSTRUCTION SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" ADOPTED JANUARY 1, 2007 THEREINAFTER REFERRED TO AS STANDARD SPECIFICATIONS. THE LATEST EDITION OF THE "ILLINOIS MANUAL ON UNIFORM MANUAL TRAFFIC CONTROL DEVICES FOR STREETS & HIGHWAYS" IN EFFECT ON THE DATE OF INVITATION FOR BIDS; THE "SUPPLEMENTAL SPECIFICATIONS & RECURRING SPECIAL PROVISIONS" ADOPTED JANUARY 1, 2011; SPECIAL PROVISIONS AS INCLUDED IN THE CONTRACT DOCUMENTS; AND THE DETAILS AND STANDARDS CONTAIN IN THESE PLANS.
- BEFORE STARTING ANY EXCAVATIONS, THE CONTRACTOR SHALL CALL "JULIE" AT 1-800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE & GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED)
- THE LOCATIONS OF THE EXISTING UTILITIES, AS SHOWN ON THE DRAWINGS, REPRESENT DATA RECEIVED FROM VARIOUS SOURCES; IT IS NOT GUARANTEED TO BE CORRECT OR ALL INCLUSIVE. THE CONTRACTOR SHALL CONDUCT HIS OWN INVESTIGATIONS INTO THE LOCATION, SIZE, DEPTH, AND NATURE OF ANY AND ALL EXISTING UTILITIES WHICH MAY INTERFERE WITH THE WORK UNDER THIS CONTRACT. ANY EXISTING UTILITIES WHICH ARE TO REMAIN IN SERVICE SHALL BE FULLY PROTECTED BY THE CONTRACTOR AND ANY DAMAGE CAUSED BY THE CONSTRUCTION SHALL BE IMMEDIATELY REPAIRED AT NO ADDITIONAL COST TO THE COUNTY.
- THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, LAKE COUNTY DIVISION OF TRANSPORTATION, AND THE VILLAGE OF BUFFALO GROVE.
- ALL WORK SHALL BE COMPLETED WITHIN THE LIMITS OF THE PROJECT SHOWN. NO EQUIPMENT, MATERIALS OR A YARD OR FIELD OFFICE SHALL BE SET UP OR STORED ON COUNTY OR PRIVATE PROPERTY WITHOUT WRITTEN PERMISSION OF THE COUNTY OR THE PROPERTY OWNER.
- BARRICADES: THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO (2) WEIGHTED SANDBAGS ON EACH TYPE II BARRICADE USED - ONE (1) WEIGHTED SANDBAG ACROSS EACH BOTTOM RAIL.
- ALL EXCAVATION AND EMBANKMENT LOCATIONS REQUIRING SEEDING OR SODDING SHALL BE CONSTRUCTED TO 6 IN BELOW FINISHED GRADE LINE TO ALLOW TOPSOIL PLACEMENT.
- PAVEMENT ELEVATIONS: THE ELEVATIONS SHOWN ON THE PLANS ARE FINISHED GRADES FOR THE PAVEMENT OR SURFACE COURSE, UNLESS OTHERWISE INDICATED.
- MAINTENANCE OF TRAFFIC-GENERAL: TRAFFIC CONDITIONS, ACCIDENTS AND OTHER UNFORESEEN EMERGENCY CONDITIONS MAY REQUIRE THE ENGINEER TO RESTRICT, MODIFY OR REMOVE LANE CLOSURES OR CHANNELIZATION SHOWN ON THE PLANS. THE CONTRACTOR SHALL RESPOND WITHIN 30 MINUTES OF THE TIME OF THE NOTIFICATION BY THE ENGINEER FOR THE MAINTENANCE OF TRAFFIC CONTROL DEVICES.
- PROTECTION OF AND RESTORATION OF TRAFFIC SIGNS: PRIOR TO THE BEGINNING OF CONSTRUCTION OPERATIONS, THE CONTRACTOR WILL PROVIDE A SIGN LOG OF ALL EXISTING SIGNS WITHIN THE LIMITS OF THE CONSTRUCTION ZONE. THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING THE ACCURACY OF THE SIGN LOG THROUGHOUT THE DURATION OF THIS PROJECT. THIS WORK IS CONSIDERED INCLUDED IN THE COST OF THE CONTRACT. ALL EXISTING TRAFFIC SIGNS SHALL MAINTAIN, FURNISH, AND REPLACE AT HIS EXPENSE, ANY TRAFFIC SIGN OR POST WHICH HAS BEEN DAMAGED OR LOST BY THE CONTRACTOR.
- TRAFFIC CONTROL DEVICES: ALL TRAFFIC CONTROL DEVICES USED FOR THE MAINTENANCE OF TRAFFIC AS DETAILED ON THE PLANS SHALL BE REFLECTORIZED PRIOR TO INSTALLATION AND CLEANED AS NECESSARY THROUGHOUT THE DURATION OF THE CONTRACT.
- DURING CONSTRUCTION OPERATIONS ANY CONSTRUCTION DEBRIS DEPOSITED IN THE FLOW LINE DRAINAGE STRUCTURE SHALL BE REMOVED AT THE CLOSE OF EACH WORKING DAY AT THE CONCLUSION OF THE CONSTRUCTION OPERATIONS. ALL DRAINAGE STRUCTURES SHALL BE CLEANED AS NECESSARY TO INSURE THAT THEY ARE FREE FROM ALL DIRT AND CONSTRUCTION DEBRIS PRIOR TO THE FINAL INSPECTION OF THE PROJECT. THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCLUDED IN THE COST OF EARTH EXCAVATION.
- OFFSETS TO DRAINAGE STRUCTURES ARE MEASURED TO THE FLOWLINE OF THE GUTTER.
- IF THE CONTRACTOR CHOOSES TO DISPOSE OF UNCONTAMINATED SOIL OR UNCONTAMINATED SOIL MIXED WITH CLEAN CONSTRUCTION AND DEMOLITION DEBRIS (CCDD) AT A CCDD FILL OPERATION, IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO PERFORM ALL NECESSARY FIELD AND LABORATORY ANALYSIS AND TO OBTAIN THE LICENSED PROFESSIONAL ENGINEER'S CERTIFICATION REQUIRED AS PER PUBLIC ACT 96-1416 TO USE THE SITE. NO ADDITIONAL COMPENSATION WILL BE PROVIDED.

15. UTILITIES CONTACTS:
- | | | |
|--|---|---|
| J.U.L.I.E.
JOINT UTILITY LOCATION FOR EXCAVATORS
(800) 892-0123 OR 811 | LAKE COUNTY DEPT OF PUBLIC WORKS
650 W. WINCHESTER ROAD
LIBERTYVILLE, IL 60048
GORDON WHITE
(847) 377-7135 | COMCAST
688 INDUSTRIAL DRIVE
ELMHURST, IL 60126
MR. ROBERT SCHULTER, JR.
(630) 600-6347 |
| ILLINOIS DEPARTMENT OF TRANSPORTATION
GEORGE GUDERLEY
AREA PERMIT COORDINATOR
201 WEST CENTER COURT
SCHAUMBURG, IL 60196
(847) 705-4131 | LAKE COUNTY DIVISION OF TRANSPORTATION
JON NELSON
ENGINEER OF TRAFFIC
(847) 377-7400 | VILLAGE OF BUFFALO GROVE
51 RAUPP BOULEVARD
BUFFALO GROVE, IL 60089
(847)459-2545 |
| NICOR GAS
90 N. FINLEY ROAD
GLEN ELLYN, IL 60137
TIM HENEHAN | COMMONWEALTH EDISON ELECTRIC COMPANY
1500 FRANKLIN BLVD.
LIBERTYVILLE, IL 60048
TIMOTHY TAMASON
(847)816-5521 | AT&T
255 E CHICAGO STREET
ELGIN, IL 60120
DON VIRMOND
(847)888-6621 |

NOTE: "THE ILLINOIS DEPARTMENT OF TRANSPORTATION IS NOT THE OWNER OF RECORD FOR THIS BRIDGE. THOSE SEEKING HISTORIC, AS-BUILT OR OTHER EXISTING DOCUMENTS AND OWNER OF RECORD PLANS MUST CONTACT THE TO MAKE ARRANGEMENTS FOR ACCESS TO THIS INFORMATION."

FILE NAME = LC8987-sht-gennote.dgn	USER NAME = 3202080907	DESIGNED - TC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, IDOT STANDARDS, AND GENERAL NOTES		F.A.J. RTE. 2626	SECTION 05-00193-04-BR	COUNTY LAKE	TOTAL SHEETS 36	SHEET NO. 2	
	PLOT SCALE = 2.0000 "/ IN.	DRAWN - PWL	REVISED -		SCALE: NTS	SHEET NO. 1 OF 1 SHEETS	STA. N/A	TO STA. N/A	CONTRACT NO. 63531			
	PLOT DATE = 11/2/2010	CHECKED - MRH	REVISED -		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT							
		DATE - 11/2/2010	REVISED -									