



Legend

- Limits of Removal of Existing Superstructure
- Limits of Concrete Removal

** Prior to Stage I Removal, a pre-construction traffic stage is necessary for the removal of 5'-5" of the northbound median. Type II barricades shall be used to maintain one lane of northbound traffic during this removal. Barricades may be adjusted in the field to facilitate median removal, as long as minimum stage construction traffic lane widths are maintained. The removal of the median and placement of Temporary Hot-Mix Asphalt shall be included in the cost of Concrete Removal.

TOTAL BILL OF MATERIAL

ITEM	UNIT	Quantity
Removal of Existing Superstructure	Each	1
Concrete Removal	Cu. Yd.	7.6

