

SUMMARY OF QUANTITIES (CONT.)

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	L05E		LICE	
				80% FED 20% STATE			
				NHS		BRRP	
		STRUCTURE 0011	ROADWAY 0004	STRUCTURE 0011	ROADWAY 0004		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2		1		1
70106700	TEMPORARY RUMBLE STRIPS	EACH	9		3		6
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,000		500		500
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	8,030		3,549		4,481
70300280	TEMPORARY PAVEMENT MARKING-LINE 24"	FOOT	50		26		24
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,409		1,552		1,857
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,712.5		737.5		975.0
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1,662.5		712.5		950.0
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	17,031		8,672		8,359
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	14		6		8
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	3		1		2
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	21		8		13
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	16		8		8
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8		4		4
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2,840		1,446		1,394
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	17		7		10
* A2006514	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	52		26		26
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	253	120		133	
X4400110	TEMPORARY PAVEMENT REMOVAL	SQ YD	756		223		533
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1,232		699		533
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1			1	
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1			1	
Z0001000	AGGREGATE FOR TEMPORARY CROSSING	TON	83		51		32
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	54	26		28	
Z0004552	APPROACH SLAB REMOVAL	SQ YD	367		140		227
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.0		0.5		0.5
Z0026407	TEMPORARY SHEET PILING	SQ FT	954	178		776	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	4		2		2
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1				1
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	4		2		2
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	284	132		152	
Z0062456	TEMPORARY PAVEMENT	SQ YD	756		223		533
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	217	217			

N/P - DENOTES NON-PARTICIPATING ITEM

* - DENOTES SPECIALTY ITEM

NHS FUNDING CATEGORY ASSOCIATED WITH PROPOSED S.N. 043-0079 IMPROVEMENT LOCATION.

BRRP FUNDING CATEGORY ASSOCIATED WITH PROPOSED S.N. 043-0078 IMPROVEMENT LOCATION.

FILE NAME =	USER NAME = costello	DESIGNED - SEW	REVISED -
C:\Documents and Settings\costello\De	ktop\IL 84\064826-sht-500.dgn	DRAWN - SEW	REVISED -
	PLOT SCALE = 50.0000' / IN.	CHECKED - FML	REVISED -
	PLOT DATE = Thu Oct 21 11:16:20 2010	DATE - 10-15-2010	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL-84 OVER TRIBUTARY TO APPLE RIVER & DUKE CREEK

SCALE: NONE SHEET NO. 2 OF 2 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
308	103BR-3 & 104BR-1	JO DAVIESS	126	4
CONTRACT NO. 64B26			ILLINOIS FED. AID PROJECT	