

IL 84 SCHEDULE OF QUANTITIES

X4400110 - TEMPORARY PAVEMENT REMOVAL

LOCATION	RT	SQ_YD	REMARK
TRIBUTARY TO APPLE RIVER			
STA. 161+23 - 164+88	RT	236	
STA. 166+25 - 170+57	RT	192	
DUKE CREEK			
STA. 336+97 - 339+69	RT	159	
		<u>587</u>	TOTAL

Z0030250 - IMPACT ATTENUATORS, TEMPORARY
(NON- REDIRECTIVE), TEST LEVEL 3

LOCATION	EACH	REMARK
TRIBUTARY TO APPLE RIVER		
JOBSITE	2	
DUKE CREEK		
JOBSITE	2	
		<u>4</u>
TOTAL	4	

Z0030350 - IMPACT ATTENUATORS, RELOCATE
(NON- REDIRECTIVE), TEST LEVEL 3

LOCATION	EACH	REMARK
TRIBUTARY TO APPLE RIVER		
JOBSITE	1	
DUKE CREEK		
JOBSITE	2	
		<u>3</u>
TOTAL	3	

Z0001000 - AGGREGATE FOR TEMPORARY CROSSING

LOCATION	ION	REMARK
TRIBUTARY TO APPLE RIVER		
Driveway @ Sta. 163+49	32	
DUKE CREEK		
Driveway @ Sta. 334+27	23	
Driveway @ Sta. 338+59	28	
		<u>83</u>
TOTAL	83	

Z0013798 - CONSTRUCTION LAYOUT

LOCATION	SUM	REMARK
JOBSITE		
	1	
		<u>1</u>
TOTAL	1	

EARTHWORK

LOCATION	PRESTAGE TEMP. PAV'T			EARTH EXCAVATION			CHANNEL EXCAVATION			FURNISHED EXCAVATION WASTE (+) SHORTAGE (-)
	20200100 EARTH EXCAVATION	EMBANKMENT	EARTH EXCAVATION ADJ. FOR SHRINKAGE	20200100 EARTH EXCAVATION	EMBANKMENT	EARTH EXCAVATION ADJ. FOR SHRINKAGE	20300100 CHANNEL EXCAVATION	EMBANKMENT	CHANNEL EXCAVATION ADJ. FOR SHRINKAGE	
TRIBUTARY TO APPLE RIVER	96	14	72	85	1813	63	2915	0	2186	+496
DUKE CREEK	24	3	18	562	437	421	594	11	446	+435

NOTE: AN ESTIMATED QUANTITY OF 2000 CU. YD. FOR FURNISHED EXCAVATION IS INCLUDED IN THE PLANS, AND SHALL BE UTILIZED ONLY AS DIRECTED BY THE ENGINEER, SHOULD IT BE DETERMINED THAT THE PROPOSED CHANNEL EXCAVATION IS NOT SUITABLE FOR USE AS FILL MATERIAL.