

SCHEDULE OF QUANTITIES
EARTHWORK SCHEDULE

Location	Remarks	Earth Excavation (CUT)	Earth Excavation Adj. Shrink 25%	Embankment (FILL)	Earthwork Balance Waste (+) Shortage (-)
		Cu Yd	Cu Yd	Cu Yd	Cu Yd
IL 82 Over Green River					
Sta 1258+10.0 - 1264+00.0	Roadway	1107.8	830.85	176.2	654.7
Sta 1264+00.0 - 1266+00.0	Bridge	0.0	0.00	0.0	0.0
Sta 1266+00.0 - 1271+25.0	Roadway	1489.5	1117.13	1153.0	-35.9
Sta 1259+98.0 - 1264+09.0	Temp. Pavement	92.8	69.60	12.8	56.9
Sta 1265+70.0 - 1270+57.0	Temp. Pavement	110.6	82.95	14.9	68.1
TOTAL		2,801.0	2,100.5	1,356.9	743.7

HMA SCHEDULE

Location	Length	Proposed Surface		44000158	40600982	40600625	40603080	40603310	40603335	42001430	48203023	Z0062456	40600990
		Width	Sq Yd	Hot-Mix Asphalt Surface Removal, 2 1/4"	Hot-Mix Asphalt Surface Removal - Butt Joint	Leveling Binder (Machine Method) N50 *	Hot Mix Asphalt Binder Course, IL-19.0, N50	Hot Mix Asphalt Surface Course, "Mix C", N50	Hot Mix Asphalt Surface Course, "Mix D", N50	Bridge Approach Pavement Connector (Flexible)	Hot Mix Asphalt Shoulders, 6 1/2"	Temporary Pavement	Temporary Ramp
				Sq Yd	Sq Yd	Ton	Ton	Ton	Ton	Sq Yd	Sq Yd	Sq Yd	Sq Yd
IL 82 - Mainline													
Sta 1259+50.0 - 1263+66.6	417	24.0	1111.0			62.2	99.0		96.1				
Sta 1263+66.6 - 1263+76.6	10	46.0	51.1							51.1			
Sta 1266+33.1 - 1266+43.1	10	46.0	51.1							51.1			
Sta 1266+43.1 - 1268+50.0	207	24.0	551.7			30.9	322.0		47.7				
Sta 1268+50.0 - 1271+25.0	275	24.0	733.3			41.1	50.0		63.4				
Hot Mix Asphalt Shoulders - RT													
Sta 1258+24.3 - 1261+32.8	308	8.0	274.2					23.7			274		
Sta 1261+32.8 - 1262+05.3			123.0					10.6			123		
Sta 1262+05.3 - 1263+66.6	161	11.0	197.2					17.1			197		
Sta 1266+43.1 - 1267+18.8	76	11.0	92.5					8.0			92		
Sta 1267+18.8 - 1267+91.3			122.0					10.6			122		
Sta 1267+91.3 - 1271+25.0	334	8.0	296.6					25.7			297		
Hot Mix Asphalt Shoulders - LT													
Sta 1259+50.0 - 1262+07.1	257	3.0	85.7					7.4			86		
Sta 1262+07.1 - 1262+90.8			130.0					11.2			130		
Sta 1262+90.8 - 1263+66.6	76	11.0	92.7					8.0			93		
Sta 1266+43.1 - 1266+79.4	36	11.0	44.3					3.8			44		
Sta 1266+79.4 - 1269+32.0			367.0					31.8			367		
Sta 1269+32.0 - 1271+25.0	193	3.0	64.3					5.6			64		
Temporary Pavement													
Sta 1259+98.0 - 1264+09.0	411		223.0									223	
Sta 1265+70.0 - 1270+57.0	487		266.0									266	
Hot Mix Asphalt Removal													
Sta 1259+50.0 - 1263+66.6	417	24.0	1111.0	1111.0									
Sta 1268+50.0 - 1271+25.0	275	24.0	733.3	733.3									
Temporary Ramp													
Sta 1261+20.0		Stage II	23.0	51.1									51.1
Sta 1269+35.0		Stage II	21.0	46.7									46.7
Sta 1259+50.0		Stage III	24.0	53.3									53.3
Sta 1271+25.0		Stage III	24.0	53.3									53.3
Hot-Mix Asphalt Surface Removal - Butt Joint													
Sta 1259+50.0 - 1259+54.5	4.50	24.0	12.0		12.0								
Sta 1271+20.5 - 1271+25.0	4.50	24.0	12.0		12.0								
TOTAL				1844	24	134	471	163	207	102	1889	489	204

* 1" Thickness calculated across entire area

FILE NAME = G:\ENR\06-6798-1A D2 Bridges Phase 2\IL82\CAD\Civil\Sheet\026425-hw-mh5.dgn



USER NAME = #USER#	DESIGNED - AAS	REVISED - -----
	DRAWN - AAS	REVISED - -----
PLOT SCALE = #SCALE#	CHECKED - KMB	REVISED - -----
PLOT DATE = 10/28/2010	DATE - 08/27/2010	REVISED - -----

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
IL 82 OVER GREEN RIVER

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
638	129BR-4	HENRY	93	10
CONTRACT NO. 64025				
ILLINOIS FED. AID PROJECT				

SCALE: SHEET NO. 5 OF 5 SHEETS STA. TO STA.