

# SCHEDULE OF QUANTITIES

## Concrete Sealer

Location	Structure No.	Facility Carried	Feature Crossed	Location	Deck Length (Ft)	Deck Width (Ft)	Parapet Lt (Ft)	Parapet Rt (Ft)	Area (Sq Ft)	TC & P
Henry County										
	037-0009	I-74 SB	Oscos Road	2 mi East of Orion	102.2	41.3	3.77	3.77	4,991	701406
	037-0010	I-74 NB	Oscos Road	2 mi East of Orion	102.1	41.3	3.77	3.77	4,987	701406
	037-0011	I-74 NB	Camp Creek	2 mi north of IL 81	127.7	40.4	3.77	3.77	6,122	701406
	037-0012	I-74 SB	Camp Creek	2 mi north of IL 81	127.7	40.4	3.77	3.77	6,122	701406
	037-0013	I-74 SB	Edwards River	2 mi south of IL 81	144.2	41	3.77	3.77	6,999	701406
	037-0014	I-74 NB	Edwards River	2 mi south of IL 81	144.2	41	3.77	3.77	6,999	701406
	037-0033	I-80 EB	Oscos Road	0.5 mi east if I-74	110.6	40	3.77	3.77	5,258	701406
	037-0034	I-80 WB	Oscos Road	0.5 mi east if I-74	110.5	52	3.77	3.77	6,579	701406
	037-0035	I-80 EB	Geneseo Creek	0.1 mi west of IL 82	207	30.3	3.77	3.77	7,833	701406 701411
	037-0036	I-80 WB	Geneseo Creek	0.1 mi west of IL 82	207	49.5	3.77	3.77	11,807	701406 701411
	037-0039	I-80 EB	Spring Creek	3.7 mi east of IL 82	140	40.6	3.77	3.77	6,740	701406
	037-0040	I-80 WB	Spring Creek	3.7 mi east of IL 82	140	40.6	3.77	3.77	6,740	701406
	037-0041	I-80 EB	TR 276	2.8 mi west Atkinson Road	117	40	3.77	3.77	5,562	701406
	037-0042	I-80 WB	TR 276	2.8 mi west Atkinson Road	117	40	3.77	3.77	5,562	701406
	037-0043	I-80 EB	US 6 & IAIS RR	3.5 mi west of IL 78	286	35.4	3.77	3.77	12,281	701406
	037-0044	I-80 WB	US 6 & IAIS RR	3.5 mi west of IL 78	286	35.4	3.77	3.77	12,281	701406
	037-0045	I-80 EB	Mud Creek	0.7 mi west of IL 78	142	40.7	3.77	3.77	6,850	701406
	037-0046	I-80 WB	Mud Creek	0.7 mi west of IL 78	142	40.7	3.77	3.77	6,850	701406
	037-0169	I-80 EB	IL 82	South edge of Geneseo	206.3	40	3.77	3.77	9,808	701406
	037-0170	I-80 WB	IL 82	South edge of Geneseo	206.3	40	3.77	3.77	9,808	701406
Whiteside County										
	098-0079	I-88 EB	Rock River	3 mi west of Rock Falls	1200	38.5	3.77	3.77	55,248	701406 701411
	098-0080	I-88 WB	Rock River	3 mi west of Rock Falls	1200	38.5	3.77	3.77	55,248	701406 701411
									260,674	

FAI 74 (I-74), FAI 80 (I-80) & FAI 88 (I-88)  
D2 Deck Sealing 2011-2  
Henry & Whiteside Counties

FILE NAME =	USER NAME = linkdj	DESIGNED -	REVISD -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Q:\BRV\CADD plans\Various Counties\2011 deck sealing\Interstate\PLANeng.dgn	DRAWN -	REVISD -										
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISD -										
PLOT DATE = Wed Oct 06 10:21:20 2010	DATE -	REVISD -										
					SCALE: _____	SHEET NO. _____ OF _____ SHEETS	STA. _____ TO STA. _____	CONTRACT NO. 64G33				
ILLINOIS FED. AID PROJECT												