

REMOVAL OF PAVING MATERIALS				
LOCATION	PAVEMENT REMOVAL	HMA SURFACE REMOVAL - BUTT JOINT	HMA SURFACE REMOVAL, VARIABLE DEPTH	HMA SURFACE REMOVAL, 1 1/2"
	SQ YD	SQ YD	SQ YD	SQ YD
STA 724+50 TO STA 725+48.45				252
STA 725+48.45 TO STA 726+08.45		160		
STA 728+19.67 TO STA 728+49.84	81			
STA 729+78.45 TO STA 729+99.67	57			
STA 732+10 TO STA 734+27.50			580	
TOTAL	138	160	580	252

DRAINAGE					
LOCATION	INLET AND PIPE PROTECTION	TY B INLET BOX, STANDARD 609006 (SPECIAL)	PIPE DRAINS 12"	CONCRETE THRUST BLOCKS	END SECTIONS 12"
	EACH	EACH	FOOT	EACH	EACH
STA 729+94.67 15' LT	1	1			
STA 729+94.67 15' LT TO STA 729+94.67 45' LT			30		
STA 729+94.67 45' LT				1	1
STA 729+94.67 15' RT	1	1			
STA 729+94.67 15' RT TO STA 729+94.67 40' RT			25		
STA 729+94.67 40' RT				1	1
TOTAL	2	2	55	2	2

GUARDRAIL				
LOCATION	GUARDRAIL REMOVAL	SPBGR, TYPE A, 6 FT POSTS	TRAF BAR TERM TY 6	TRAF BAR TERM TY 1 SPL FLR
	FOOT	FOOT	EACH	EACH
STA 725+78.90 RT TO STA 728+70.70 RT	292			
STA 725+84.10 RT TO STA 726+34.42 RT				1
STA 726+34.42 RT TO STA 727+96.92 RT		162.5		
STA 726+47.45 LT TO STA 726+96.92 LT				1
STA 726+92.80 LT TO STA 728+70.80 LT	172			
STA 726+96.92 LT TO STA 727+96.92 LT		100		
STA 727+96.92 RT TO STA 728+40.67 RT			1	
STA 727+96.92 LT TO STA 728+40.67 LT			1	
STA 729+57.50 LT TO STA 732+46.60 LT	290			
STA 729+57.50 RT TO STA 731+35.10 RT	178			
STA 729+74.11 LT TO STA 730+17.86 LT			1	
STA 729+74.11 RT TO STA 730+17.86 RT			1	
STA 730+17.86 LT TO STA 731+80.36 LT		162.5		
STA 730+17.86 RT TO STA 731+17.86 RT		100		
STA 731+17.86 RT TO STA 731+67.86 RT				1
STA 731+80.36 LT TO STA 732+30.36 LT				1
TOTAL	932	525	4	4

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	
LOCATION	EACH
STA 724+00 32' LT	1
STA 724+00 32' RT	1
STA 725+00 55' LT	1
STA 725+00 55' RT	1
STA 732+00 55' LT	1
STA 732+00 55' RT	1
STA 733+00 32' LT	1
STA 733+00 32' RT	1
TOTAL	8

EPOXY PAVEMENT MARKING - LINE		
LOCATION	4"	6"
	FOOT	FOOT
STA 724+50 TO STA 734+27.50	978	250
STA 724+50 LT TO STA 734+27.50 LT	978	
STA 724+50 RT TO STA 734+27.50 RT	978	
TOTAL	2,934	250

REFLECTORS/MARKERS					
LOCATION	DELINEATORS	GUARDRAIL MARKERS	TERMINAL MARKER - DIRECT APPLIED	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKERS
	EACH	EACH	EACH	EACH	EACH
STA 724+50 TO STA 734+27.50				14	14
STA 724+50 LT TO STA 734+27.50 LT	6				
STA 724+50 RT TO STA 734+27.50 RT	6				
STA 725+84.10 RT			1		
STA 725+84.10 RT TO STA 728+40.67 RT		5			
STA 726+47.45 LT			1		
STA 726+47.45 LT TO STA 728+40.67 LT		4			
STA 729+74.11 LT TO STA 732+30.36 LT		5			
STA 729+74.11 RT TO STA 731+67.86 RT		4			
STA 731+67.86 RT			1		
STA 732+30.36 LT			1		
TOTAL	12	18	4	14	14

FILE NAME =	USER NAME = #USER#	DESIGNED - JML	REVISED -
#FILE#		DRAWN - JJO	REVISED -
	PLOT SCALE = #SCALE#	CHECKED - MSW	REVISED -
	PLOT DATE = #DATE#	DATE - 10/08/10	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1249	(23 BR/BR	BUREAU	39	8
CONTRACT NO. 66909				
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

FARNSWORTH GROUP, INC.

CONSULTING ENGINEERS - 2709 MCGRAW DRIVE BLOOMINGTON, ILLINOIS 61704 (309) 663-8435 / (309) 663-1571 FAX