

80% FEDERAL  
20% STATE

CODE NUMBER	ITEM	UNIT	TOTAL	ROADWAY 0004	STRUCTURE NO. 006-0104 (EX) 006-0181 (PR) 0011
51202305	DRIVING PILES	FOOT	645		645
51203800	TEST PILE STEEL HP14x73	EACH	2		2
51500100	NAME PLATES	EACH	1		1
52100520	ANCHOR BOLTS, 1"	EACH	36		36
54213447	END SECTIONS 12"	EACH	2	2	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	66		66
60100945	PIPE DRAINS 12"	FOOT	55	55	
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	138		138
X6090150	TYPE B INLET BOX, STANDARD 609006 (SPECIAL)	EACH	2	2	
60900515	CONCRETE THRUST BLOCKS	EACH	2	2	
63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	350	350	
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	1,094	1,094	
63500105	DELINEATORS	EACH	10	10	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	86	86	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	

• SPECIALTY ITEM

80% FEDERAL  
20% STATE

CODE NUMBER	ITEM	UNIT	TOTAL	ROADWAY 0004	STRUCTURE NO. 006-0104 (EX) 006-0181 (PR) 0011
70300100	SHORT TERM PAVEMENT MARKING	FOOT	780	780	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	8,344	8,344	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	26	26	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,093	3,093	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	850	850	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	825	825	
78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	2,799	2,799	
78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	250	250	
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	14	14	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	14	14	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	14	14	
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	22		22
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
X0322584	REVTMENT MAT REMOVAL	SQ YD	204	204	
X0323265	REMOVE EXISTING RIPRAP	SQ YD	212	212	
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	1,149		1,149
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1		1

• SPECIALTY ITEM

FILE NAME =	USER NAME = schwenkerg	DESIGNED - JML	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci\pwork\pwork\schwenkerg\d0114884\066910-sht-500.dgn	PLT SCALE = 1:8000' / IN.	DRAWN - JJO	REVISED -						698	(101 BR)BR	BUREAU	47	4
PLT DATE = Oct 21, 2010 - 04:17:09 PM	DATE - 10/08/10	CHECKED - MSW	REVISED -		CONTRACT NO. 66910				FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
		DATE - 10/08/10	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	REVISIO: 10/21/10 IDOT 24-8371			