



NOTES:

1. TEMPORARY FENCE SHALL BE A HIGH VISIBILITY FENCE TO PROTECT WETLAND AREA.
2. ALL SEDIMENT AND EROSION CONTROL SYSTEMS SHALL BE CONSTRUCTED WITHIN THE RIGHT-OF-WAY OR TEMPORARY EASEMENT.
3. ALL SEDIMENT AND EROSION CONTROL SYSTEMS SHALL BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER EACH 1/2" OR GREATER RAIN EVENT.

LEGEND

- ◇ (with diamond) TEMPORARY DITCH CHECK @ 35' SPACING UNLESS OTHERWISE NOTED
- ◇ (with cross) INLET AND PIPE PROTECTION
- xxx — PERIMETER EROSION BARRIER
- xxx — xx TEMPORARY FENCE AND PERIMETER EROSION BARRIER
- (with dots) TEMPORARY EROSION CONTROL SEEDING, EROSION CONTROL BLANKET & SEEDING, CLASS 1
- (with dots and cross-hatch) TEMPORARY EROSION CONTROL SEEDING, EROSION CONTROL BLANKET & SEEDING, CLASS 3
- (with cross-hatch) TEMPORARY EROSION CONTROL SEEDING, HEAVY DUTY EROSION CONTROL BLANKET (7' WIDTH) AND SEEDING CLASS 3
- (with circles) STONE RIPRAP, CLASS A4 & FILTER FABRIC
- LIMITS OF CONSTRUCTION
- ⊗ (SIZE) TREE REMOVAL

FILE NAME = #FILE#	USER NAME = #USER#	DESIGNED - JML	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	EROSION CONTROL				F.A.P. RTE. 698	SECTION (101 BR)BR	COUNTY BUREAU	TOTAL SHEETS 47	SHEET NO. 14
	PLOT SCALE = #SCALE#	DRAWN - JJO	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO. 66910			
	PLOT DATE = #DATE#	CHECKED - MSW	REVISED -						FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			
		DATE - 10/08/10	REVISED -										