

SUMMARY OF QUANTITIES				ROADWAY FAP 310 (US 67) 80% FEDERAL 20% STATE	STRUCTURE SN 094-0051 80% FEDERAL 20% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				0004	0011
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	1	1	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	8	8	
70106700	TEMPORARY RUMBLE STRIPS	EACH	6	6	
<del>70106800</del>	<del>CHANGEABLE MESSAGE SIGN</del>	<del>CAL MO</del>	<del>0.5</del>	<del>0.5</del>	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	124	124	
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	3753	3753	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1076	1076	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	800	800	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	763	763	
78001110	* PAINT PAVEMENT MARKING - LINE 4"	FOOT	3800	3800	
78100100	* RAISED REFLECTIVE PAVEMENT MARKER	EACH	9	9	
78100105	* RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	3	3	
78200410	* GUARDRAIL MARKERS, TYPE A	EACH	16	16	
78201000	* TERMINAL MARKER-DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SO FT	588	588	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	12	12	
X0321750	REMOVE TEMPORARY CONCRETE BARRIER, STATE OWNED	FOOT	200	200	
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	155		155
X4401198	HOT MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	726	726	
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1		1
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1		1
X7016500	TEMPORARY BRIDGE TRAFFIC SIGNALS (SPECIAL)	EACH	1	1	
Z0001002	GUARDRAIL AGGREGATE EROSION CONTROL	TON	272	272	
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	52		52
Z0004552	APPROACH SLAB REMOVAL	SO YD	220	220	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0034105	MATERIAL TRANSFER DEVICE	TON	311	311	
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	159		159
Z0065000	* SETTING PILES IN ROCK	EACH	20		20
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SO FT	903		903
X7016510	TEMPORARY BRIDGE TRAFFIC SIGNALS (SPECIAL) LOCATION 1	EACH	1	1	

\* SPECIALTY ITEM

FILE NAME =	USER NAME = rmbredie	DESIGNED RMB	REVISED -
S:\237\2008\23708002\US67CedarCreek\CA	D:\CADD Sheets\0468661-sht-500.dgn	DRAWN BAB	REVISED -
	PLOT SCALE = 40.0000' / IN.	CHECKED RJA	REVISED -
	PLOT DATE = 10/23/2010	DATE 09-27-2010	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

US 67 OVER CEDAR CREEK  
SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	(288)BR-1	WARREN	71	4
SCALE:			SHEET NO. OF SHEETS	
			CONTRACT NO. 68661	
ILLINOIS FED. AID PROJECT				