

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION			FURNISHED EXCAVATION WASTE (+) SHORTAGE (-) (CU YD)
	EARTH EXCAVATION (CU YD)	EMBANKMENT (CU YD)	EARTH EXCAVATION ADJ. FOR SHRINKAGE (CU YD)	
US24 OVER LAMARSH CREEK	1742	2368	1307	-1061

REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL

JOB SITE	50	CU YD

CHANNEL EXCAVATION

JOB SITE	480	CU YD

NITROGEN FERTILIZER NUTRIENT

SEEDING, CLASS 2A	1.47	ACRE
Application Rate = 90 # / Acres		
Quantity	132	POUND

PHOSPHOROUS FERTILIZER NUTRIENT

SEEDING, CLASS 2A	1.47	ACRE
Application Rate = 90 # / Acres		
Quantity	132	POUND

POTASSIUM FERTILIZER NUTRIENT

SEEDING, CLASS 2A	1.47	ACRE
Application Rate = 90 # / Acres		
Quantity	132	POUND

INCIDENTAL HOT-MIX ASPHALT SURFACING

LOCATION	TON
STAGE 1 Cameron Lane	10
STAGE 2 Cameron Lane	10
STAGE 2 Wheeler Road	5
TOTAL	25

TRENCH BACKFILL

STORM SEWERS	969	CU YD
CULVERT	122	CU YD
TOTAL	1091	CU YD

TOPSOIL FURNISH AND PLACE, 4"

STATION	LENGTH	DISTANCE	AVERAGE LENGTH	AREA
	FT	FT	FT	SQ YD
US24				
330+50.00	0.82			
		50.00	1.28	7.12
331+00.00	1.74			
		50.00	6.02	33.42
331+50.00	10.29			
		50.00	20.24	112.46
332+00.00	30.20			
		50.00	45.86	254.79
332+50.00	61.53			
		50.00	58.72	326.22
333+00.00	55.91			
		50.00	56.23	312.41
333+50.00	56.56			
		50.00	60.67	337.06
334+00.00	64.79			
		50.00	60.78	337.67
334+50.00	56.77			
		50.00	57.02	316.80
335+00.00	57.27			
		50.00	28.64	159.09
335+50.00	0.00			
		50.00	20.86	115.89
336+00.00	41.72			
		50.00	49.28	273.75
336+50.00	56.83			
		50.00	51.57	286.49
337+00.00	46.31			
		8.53	46.31	43.88
337+08.53	46.31			
		162.72	46.23	835.94
338+71.25	46.16			
		28.75	46.67	149.09
339+00.00	47.18			
		50.00	68.03	377.94
339+50.00	88.87			
		50.00	63.34	351.91
340+00.00	37.81			
		50.00	26.32	146.23

TOPSOIL FURNISH AND PLACE, 4" (CONT'D)

STATION	LENGTH	DISTANCE	AVERAGE LENGTH	AREA
	FT	FT	FT	SQ YD
US24				
340+50.00	14.83			
		50.00	16.02	89.00
341+00.00	17.21			
		50.00	31.11	172.82
341+50.00	45.01			
		50.00	41.93	232.96
342+00.00	38.86			
		50.00	40.80	226.67
342+50.00	42.74			
		50.00	32.73	181.86
343+00.00	22.73			
		50.00	18.98	105.42
343+50.00	15.22			
		22.00	7.61	18.61
343+72.00	0.00			
Cameron Lane				
8+50.00	30.88			
		50.00	19.37	107.64
9+00.00	7.87			
		50.00	10.95	60.83
9+50.00	14.03			
		9.84	7.02	7.67
9+59.84	0.00			
		74.73	0.00	0.00
10+34.57	0.00			
		15.43	18.41	31.56
10+50.00	36.82			
		50.00	29.03	161.25
11+00.00	21.23			
		50.00	46.77	259.84
11+50.00	72.31			
		50.00	59.96	333.10
12+00.00	47.60			
		61.17	23.80	161.77
12+61.17	0.00			
Wheeler Road				
18+00.00	6.12			
		50.00	14.57	80.94
18+50.00	23.02			
		50.00	14.20	78.91
19+00.00	5.39			
		61.00	2.69	18.25
19+61.00	0.00			
TOTAL				7107

DATE	BY	REVISION

DATE	BY	REVISION