

## SAW CUT JOINT DETAIL

US ROUTE 24: STA. 332+00.00 (E.B) STA. 330+38.00 (W.B.) STA. 343+72.00 (E.B.) STA. 343+50.00 (W.B.)

## NOTES FOR SAW CUT JOINT:

- SURFACE REMOVAL WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER SQUARE YARD FOR HOT-MIX
  ASPHALT SURFACE REMOVAL, VARIABLE DEPTH, AT LOCATIONS AS SPECIFIED IN THE PLANS. THIS WORK
  SHALL BE PERFORMED IN ACCORDANCE WITH THE APPLICABLE PORTIONS OF SECTION 406.
- 2. THE SAW CUT JOINT AND THE BASE SHALL BE PRIMED JUST PRIOR TO THE PLACING OF HOT MIX ASPHALT MATERIAL. THE WORK WILL BE IN ACCORDANCE WITH THE APPLICABLE PORTIONS OF ARTICLE 406.06.
- 3. COMPOSTIONS AND DIMENSIONS SHOWN IN ABOVE DETAIL ARE FOR MAINLINE US ROUTE 24. SAW CUT JOINTS SHALL ALSO BE PROVIDED FOR CAMERON LANE AND WHEELER ROAD PROJECT LIMITS. SEE PROPOSED TYPICAL SECTIONS SHEETS FOR PROPOSED PAVEMENT COMPOSITIONS FOR THE SIDEROADS.

		the state of the control of the state of the					TEADI	TOTAL SHEET
F	ILE NAME =	USER NAME = \$USER\$	DESIGNED - SEW	REVISED -	[사진 항공 사람들이 좀 맞을 봤었다. 하고 생물하다 하고 말하는 물리에서 하고 있는데 되지 않는데 사람들이 사람들이 없었다.	SAW CUT JOINT DETAIL	RTE. SECTION	COUNTY SHEETS NO.
•	FILEL#		DRAWN - SEW	REVISED -	STATE OF ILLINOIS	US ROUTE 24 OVER LAMARSH CREEK	317 45BR-2	PEORIA 122 48
₹.		PLOT SCALE = @SCALE®	CHECKED - FML	REVISED -	DEPARTMENT OF TRANSPORTATION			CONTRACT NO. 68719
		PLOT DATE = DATE	DATE - 10-15-2010	REVISED -	SCALE: NONE	SHEET NO. 1 OF 1 SHEETS STA. TO STA.	FED. ROAD DIST. NO.   ILLINOIS FED. AL	