

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY	STRUCTURE
				FAS 1360 80% FEDERAL 20% STATE	S.N. 102-0069 80% FEDERAL 20% STATE
				CONSTRUCTION TYPE CODE	
				0004	0011
20200100	EARTH EXCAVATION	CU YD	571	571	
20300100	CHANNEL EXCAVATION	CU YD	412	412	
20400800	FURNISHED EXCAVATION	CU YD	658	658	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3445	3445	
* 25000210	SEEDING, CLASS 2A	ACRE	0.8	0.8	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	72	72	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	72	72	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	72	72	
* 25100115	MULCH, METHOD 2	ACRE	0.8	0.8	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	320	320	
28000305	TEMPORARY DITCH CHECKS	FOOT	165	165	
28000400	PERIMETER EROSION BARRIER	FOOT	1368	1368	
28000500	INLET AND PIPE PROTECTION	EACH	1	1	
28100109	STONE RIPRAP, CLASS A5	SQ YD	2125		2125
28100227	STONE RIPRAP, CLASS B4	TON	975	975	
28200200	FILTER FABRIC	SQ YD	3590	1465	2125
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	133	133	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	51	51	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	10	10	
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	0.6	0.6	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	345	345	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	209	209	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	133	133	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	111	111	
44004000	PAVED DITCH REMOVAL	FOOT	827	827	
44004250	PAVED SHOULDER REMOVAL	SQ YD	224	224	
48100700	AGGREGATE SHOULDERS, TYPE A 8"	SQ YD	159	159	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	552	552	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50104650	SLOPE WALL REMOVAL	SQ YD	1328		1328
50105220	PIPE CULVERT REMOVAL	FOOT	130	130	

#SPECIALTY ITEM

USER NAME = #USER#	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 1/8" = 1' / IN.	CHECKED -	REVISED -
PLOT DATE = 10/27/2010	DATE -	REVISED -



**Allen Henderson & Associates, Inc.**  
Civil and Structural Engineers Springfield, IL.  
62703 Phone: (217)544-8033 IL Design Firm  
No. 184-001907

**SUMMARY OF QUANTITIES**

SCALE: NONE	SHEET NO. 1 OF 3 SHEETS	STA.	TO STA.
-------------	-------------------------	------	---------

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1360	(64-B-1)BR	WOODFORD	45	3
CONTRACT NO. 68785				
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				