

				ROADWAY FAS 1360 80% FEDERAL 20% STATE	STRUCTURE S.N. 102-0069 80% FEDERAL 20% STATE
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				0004	0011
50200100	STRUCTURE EXCAVATION	CU YD	64		64
50300225	CONCRETE STRUCTURES	CU YD	65.2		65.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	303.5		303.5
50300260	BRIDGE DECK GROOVING	SQ YD	597		597
50300280	CONCRETE ENCASEMENT	CU YD	5.6		5.6
50300300	PROTECTIVE COAT	SQ YD	761		761
50400735	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS 63"	FOOT	824		824
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	69790		69790
50800515	BAR SPLICERS	EACH	64		64
51201500	FURNISHING STEEL PILES HP10X57	FOOT	656		656
51202305	DRIVING PILES	FOOT	656		656
51203500	TEST PILE STEEL HP 10X57	EACH	1		1
51204650	PILE SHOES	EACH	16		16
51500100	NAME PLATES	EACH	1		1
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2	2	
54020503	PRECAST CONCRETE BOX CULVERTS 5' X 3' (M273)	FOOT	46	46	
542A1060	PIPE CULVERTS, CLASS A, TYPE 2 15"	FOOT	40	40	
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	107		107
60208250	CATCH BASINS, TYPE C, TYPE 37M GRATE	EACH	1	1	
60500050	REMOVING CATCH BASINS	EACH	1	1	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	512.5	512.5	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2	
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	2	2	
63200310	GUARDRAIL REMOVAL	FOOT	794	794	
66700205	PERMANENT SURVEY MARKERS, TYPE 1	EACH	1		1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	0.5	0.5	

*SPECIALTY ITEM

USER NAME = *USER*	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 10.0000 ' / IN.	CHECKED -	REVISED -
PLOT DATE = 10/27/2010	DATE -	REVISED -



Allen Henderson & Associates, Inc.
Civil and Structural Engineers Springfield, IL
62703 Phone: (217)544-8033 IL Design Firm
No. 184-001907

SUMMARY OF QUANTITIES			
SCALE: NONE	SHEET NO. 2 OF 3 SHEETS	STA.	TO STA.

F.A.S. RTE. 1360	SECTION (64-B-1)BR	COUNTY WOODFORD	TOTAL SHEETS 45	SHEET NO. 4
CONTRACT NO. 68785				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				