

SEEDING SCHEDULE					
LOCATION	SEEDING, CLASS 2A	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH, METHOD 2
	ACRE	POUND	POUND	POUND	ACRE
STA 950+50 TO STA 954+34.25 LT	0.20	18.00	18.00	18.00	0.20
STA 955+73.25 TO STA 958+50 LT	0.15	13.50	13.50	13.50	0.15
STA 950+50 TO STA 954+34.25 RT	0.30	27.00	27.00	27.00	0.30
STA 955+73.25 TO STA 958+50 RT	0.15	13.50	13.50	13.50	0.15
TOTAL	0.80	72	72	72	0.80

EARTHWORK SCHEDULE					
LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJ FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISH AND PLACE, 4"
	CU YD	CU YD	CU YD	CU YD	SO YD
STA 950+50 TO STA 954+44.25	360	270	547	-277	1935
STA 955+63.25 TO STA 958+50	211	158	539	-381	1510
TOTAL	571	428	1086	-658	3445

HMA PAVEMENT SCHEDULE		
LOCATION	HMA BINDER CRSE, IL-19.0, N50	HMA SURFACE CRSE, MIX "D", N50
	TON	TON
STA 950+50 TO STA 953+98.75		78.5
STA 956+08.75 TO STA 958+50		54.5
STA 952+96 TO STA 953+30	11.6	
STA 953+30 TO STA 953+98.75	143.2	
STA 956+08.75 TO STA 956+29	42.2	
STA 956+29 TO STA 956+64	12.0	
TOTAL	209	133

POLMERIZED BITUMINOUS MATERIALS (PRIME COAT) SCHEDULE	
LOCATION	QUANTITY
	TON
STA 950+50 TO STA 953+30 (MILLED)	0.25
STA 952+96 TO STA 954+14.25 (FOG)	0.06
STA 953+30 TO STA 953+98.75 (EX PVMT)	0.04
STA 955+93.25 TO STA 956+64 (FOG)	0.04
STA 956+08.75 TO STA 956+29 (EX PVMT)	0.01
STA 956+29 TO STA 958+50 (MILLED)	0.20
TOTAL	0.60

PAVEMENT MARKING SCHEDULE		
LOCATION	EPOXY PAVEMENT MARKING	
	SKIP-DASH (10'/30') YELLOW 4"	SOLID WHITE 4"
	FOOT	FOOT
STA 950+50 TO STA 958+50 LT		800
STA 950+50 TO STA 958+50 CENTERLINE	200	
STA 950+50 TO STA 958+50 RT		800
SUB-TOTAL	200	1600
TOTAL		1800

SUB-BASE GRANULAR MATERIAL, TYPE A SCHEDULE	
LOCATION	QUANTITY
	TON
STA 953+98.75 TO STA 954+11.25	43
STA 954+21.25 TO STA 954+34.11	35
STA 955+78.25 TO STA 955+86.25	22
STA 955+96.25 TO STA 956+08.75	33
TOTAL	133

BRDG APPR PVMT CONN (FLEX) SCHEDULE	
LOCATION	QUANTITY
	SO YD
STA 953+98.75 TO STA 954+14.25	55.5
STA 955+93.25 TO STA 956+08.75	55.5
TOTAL	111

CHANNEL EXCAVATION SCHEDULE	
LOCATION	QUANTITY
	CU YD
STA. 954+44.25 TO STA. 955+63.25, 67.5 LT TO 69' RT	412
TOTAL	412

REMOVAL ITEMS SCHEDULE							
LOCATION	PAVED SHOULDER REMOVAL	PAVED DITCH REMOVAL	APPR SLAB REMOVAL	HMA SURF REMOVAL - BUTT JOINT	HMA SURF REMOVAL - VAR DEPTH	PIPE CULVERT REMOVAL	REMOVAL CATCH BASINS
	SO YD	FOOT	SO YD	SO YD	SO YD	FOOT	EACH
STA 950+50 TO STA 950+80				80			
STA 950+80 TO STA 952+96					576		
STA 952+96 TO STA 953+30				91			
STA 956+29 TO STA 956+64				94			
STA 956+64 TO STA 958+20					416		
STA 958+20 TO STA 958+50				80			
STA 953+98.75 TO STA 954+38.75			107				
STA 955+68.75 TO STA 956+08.75			107				
STA 950+50 TO STA 954+38.75 LT & RT	130						
STA 955+68.75 TO STA 958+50 LT & RT	94						
STA 951+00 TO STA 951+29 LT		29					
STA 951+77 TO STA 954+35 LT		258					
STA 956+13 TO STA 957+45 LT		132					
STA 952+00 TO STA 954+02 RT		202					
STA 955+92 TO STA 957+88 RT		206					
PE STA 951+51 LT, 30" CMP						46	
PE STA 951+51 LT, 42" CMP						46	
PE STA 957+64 LT, 12" RCCP						38	
STA 957+81, 32.4' LT							1
TOTAL	224	827	214	345	992	130	1

SHOULDER SCHEDULE			
LOCATION	AGGREGATE SHOULDERS, TY A 8"	GUARDRAIL AGG EROS CONTROL	HMA SHOULDERS, 8"
	SO YD	TON	SO YD
STA 950+50 TO STA 951+12.5 LT	25.5		
STA 951+67.65 TO STA 952+48.60 LT	51.0		
STA 952+48.60 TO STA 954+14.25 LT		41	
STA 955+93.25 TO STA 957+57.62 LT		42	
STA 957+77.60 TO STA 958+50 LT	31.5		
STA 950+50 TO STA 951+23.60 RT	32.7		
STA 951+23.60 TO STA 954+14.25 RT		59	
STA 955+93.25 TO STA 958+08.90 RT		44	
STA 958+08.90 TO STA 958+50 RT	18.3		
STA 950+50 TO STA 953+98.75 LT			182.6
STA 956+08.75 TO STA 958+50 LT			107.2
STA 950+50 TO STA 953+98.75 RT			155.0
STA 956+08.75 TO STA 958+50 RT			107.2
TOTAL	159	186	552

AGG SURF CRSE, TY B SCHEDULE	
LOCATION	QUANTITY
	TON
PE STA 951+52.2 LT	28
PE STA 957+64.6 LT	23
TOTAL	51

MATERIAL TRANSFER DEVICE SCHEDULE	
LOCATION	QUANTITY
	TON
STA. 950+50 TO STA. 952+96	55.5
STA. 952+96 TO STA. 953+98.75	58.4
STA. 956+08.75 TO STA. 956+64	31.4
STA. 956+64 TO STA. 958+50	42
TOTAL	187.3

FILE NAME = Z:\2008 Jobs\08-027\CADD Sheets\0468785-sht-sched.dgn

USER NAME = #USER#
 PLOT SCALE = 2.0000 "/ IN.
 PLOT DATE = 10/27/2010

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -

REVISED -
 REVISED -
 REVISED -
 REVISED -



Allen Henderson & Associates, Inc.
 Civil and Structural Engineers Springfield, IL
 62703 Phone: (217)544-8033 IL Design Firm
 No. 184-001907

SCHEDULE OF QUANTITIES
 SCALE: NONE SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1360	(64-B-1)BR	WOODFORD	45	8
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
CONTRACT NO. 68785				