

GUARDRAIL SCHEDULE						
LOCATION	SPBGR TY A, 6' POSTS	TBT, TY 6	TBT, TY 1 (SPECIAL) TANGENT	TBT, TY 1 (SPECIAL) FLARED	GUARDRAIL REMOVAL	TERMINAL MARKER- DIRECT APPLIED
	FOOT	EACH	EACH	EACH	FOOT	EACH
STA 952+48.60 LT						1
STA 952+48.60 TO STA 952+98.60 LT				1		
STA 952+98.60 TO STA 953+86.10 LY	87.5					
STA 953+86.10 TO STA 954+29.25 LT		1				
STA 955+78.25 TO STA 956+21.40 LT		1				
STA 956+21.40 TO STA 956+96.40 LT	75					
STA 956+96.40 TO STA 957+46.40 LT				1		
STA 957+46.40 LT						1
STA 951+23.60 RT						1
STA 951+23.60 TO STA 951+73.60 RT			1			
STA 951+73.60 TO STA 953.86.10 RT	212.5					
STA 953+86.40 TO STA 954.29.25 RT		1				
STA 955+78.25 TO STA 956+21.40 RT		1				
STA 956+21.40 TO STA 957+58.90 RT	137.5					
STA 357+58+90 TO STA 958+08.90 RT			1			
STA 958+00 TO STA 08.90 RT						1
STA 955+70 TO STA 954+37 LT					187	
STA 955+70 TO STA 957+44 LT					174	
STA 951+90 TO STA 954+37 RT					247	
STA 95+70 TO STA 957.56					186	
TOTAL	512.5	4	2	2	794	4

DRAINAGE STRUCTURES SCHEDULE					
LOCATION	BOX CULV END SECTIONS, CULV NO. 1	PRECAST CONC BOX CULV 5'X3' (M273)	PIPE CULV, TY 2 RCCP 15"	PRCFES 15"	CATCH BASIN, TY C, TY 37M GRATE
	EACH	FOOT	FOOT	EACH	EACH
STA 951+30 LT	1				
STA 951+30 TO 951+75.8 LT		46			
STA 951+75.8 LT	1				
STA 957+41.8 LT				1	
STA 957+41.8 TO STA 957+81.0			40		
STA 957+81.0 LT					1
TOTAL	2	46	40	1	1

RAISED REFLECTIVE PAVEMENT MARKER SCHEDULE		
LOCATION	RRPM	RRPM REMOVAL
	EACH	EACH
STA 950+50 TO STA 954+14.25	5	5
STA 954+14.25 TO STA 955+93.25		2
STA 955+53.25 TO STA 958+50	4	4
TOTAL	9	11

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -
Z:\2008 Jobs\08-027\CADD Sheets\0468785	ah-sched.dgn	DRAWN -	REVISED -
	PLOT SCALE = 2.0000 / / IN.	CHECKED -	REVISED -
	PLOT DATE = 10/25/2010	DATE -	REVISED -



Allen Henderson & Associates, Inc.
 Civil and Structural Engineers Springfield, IL.
 62703 Phone: (217)544-8033 IL Design Firm
 No. 184-001907

SCALE: NONE		SHEET NO. 2 OF 2 SHEETS		STA.	TO STA.
-------------	--	-------------------------	--	------	---------

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1360	(64-B-1)BR	WOODFORD	45	9
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				

SCHEDULE OF QUANTITIES

CONTRACT NO. 68785