


RIPRAP SCHEDULE

LOCATION	STONE RIPRAP, CLASS B4	STONE RIPRAP, CLASS A5	FILTER FABRIC
	TON	SQ YD	SQ YD
STA. 951+00 TO STA. 951+24 LT.	38		57
STA. 951+81 TO STA. 954+34.25 LT.	285.5		429
STA. 955+73.25 TO STA. 957+42 LT.	169.5		255
STA. 952+00 TO STA. 954+34.25	245		368
STA. 955+73.25 TO STA. 958+00 RT.	237		356
STA. 954+34.25 TO STA. 955+73.25, 67.5' LT. TO 69' RT.		*2125	*2125
TOTAL	975	2125	3590

*STRUCTURE PAY ITEM



TEMPORARY EROSION CONTROL ITEMS SCHEDULE

LOCATION	TEMP EROS CONTROL SEEDING (4 APPLICATIONS)	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET & PIPE PROTECTION
	POUND	FOOT	FOOT	EACH
STA. 950+50 TO STA. 954+34.25 LT.	20x4 = 80			
STA. 955+73.25 TO STA. 958+50 LT.	15x4 = 60			
STA. 950+50 TO STA. 954+34.25 RT.	30x4 = 120			
STA. 955+73.25 TO STA. 958+50 RT.	15x4 = 60			
STA. 952+00 LT. & RT.		30		
STA. 953+00 LT. & RT.		30		
STA. 954+00 LT. & RT.		30		
STA. 956+00 LT. & RT.		30		
STA. 957+00 LT. & RT.		30		
STA. 958+00 LT. & RT.		15		
STA. 951+67 TO STA. 954+76 LT.			309	
STA. 955+32 TO STA. 957+58 LT.			227	
STA. 957+73 TO STA. 958+50 LT.			84	
STA. 950+50 TO STA. 954+76 RT.			428	
STA. 955+32 TO STA. 958+50 RT.			320	
STA. 957+81, 32.5' LT.				1
TOTAL	320	165	1368	1

LEGEND

- TEMPORARY DITCH CHECK
- INLET & PIPE PROTECTION
- PERIMETER EROSION BARRIER
- *STONE RIPRAP, CLASS A5
- STONE RIPRAP, CLASS B4
- TEMPORARY EROSION CONTROL SEEDING

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

Allen Henderson & Associates, Inc.
 Civil and Structural Engineers Springfield, IL
 62703 Phone: (217)544-8033 IL Design Firm
 No. 184-001907

EROSION CONTROL PLAN				
SCALE: 1"=50'	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	
F.A.S. RTE. 1360	SECTION (64-B-1)BR	COUNTY WOODFORD	TOTAL SHEETS 45	SHEET NO. 14
			CONTRACT NO. 68785	
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				