

SUMMARY OF QUANTITIES

LOCATION:

FUNDING BREAKOUT:

CONSTRUCTION CODE:

PIATT COUNTY RURAL
80% FEDERAL 20% STATE
0005

PIATT COUNTY RURAL
50% BEMENT 50% STATE
0005

SUMMARY OF QUANTITIES

LOCATION:

FUNDING BREAKOUT:

CONSTRUCTION CODE:

PIATT COUNTY RURAL
80% FEDERAL 20% STATE
0005

PIATT COUNTY RURAL
50% BEMENT 50% STATE
0005

PAY ITEM CODE	PAY ITEM	UNIT	TOTAL	QTY	QTY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	12,460.0	12,460.0	
40600300	AGGREGATE (PRIME COAT)	TON	200.0	200.0	
40600895	CONSTRUCTING TEST STRIP	EACH	1.0	1.0	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	84.0	84.0	
40600990	TEMPORARY RAMP	SQ YD	95.0	95.0	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	10468.0	9819.0	649.00
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	600.0	600.0	
40800030	AGGREGATE (PRIME COAT)	TON	10.0	10.0	
40800050	INCIDENTAL HOT MIX ASPHALT SURFACING	TON	504.0	504.0	
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	103,911.0	103,911.0	
44000154	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/4"	SQ YD	20,606.0	12,883.0	7723.0
44000400	GUTTER REMOVAL	FOOT	458.0	458.0	
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	21,106.0	21,106.0	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	77.0	77.0	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	10,553.0	10,553.0	
* 56109210	WATER VALVES TO BE ADJUSTED	EACH	5.0	5.0	
60255500	MANHOLES TO BE ADJUSTED	EACH	19.0	19.0	
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	18.0	18.0	

PAY ITEM CODE	PAY ITEM	UNIT	TOTAL	QTY	QTY
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	2.0	2.0	
67100100	MOBILIZATION	L SUM	1.0	1.0	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0	1.0	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	1.0	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.0	1.0	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	11,084.0	11,084.0	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQFT	1,280.0	1,280.0	
* 78000100	THERMOPLASTIC PAVEMENT MARKING-LETTERS AND SYMBOLS	SQFT	127.0	127.0	
* 78000200	THERMOPLASTIC PAVEMENT MARKING-LINE 4"	FOOT	3,324.0	3324.0	
* 78000400	THERMOPLASTIC PAVEMENT MARKING-LINE 6"	FOOT	84.0	84.0	
* 78000600	THERMOPLASTIC PAVEMENT MARKING-LINE 12"	FOOT	165.0	165.0	
* 78000650	THERMOPLASTIC PAVEMENT MARKING-LINE 24"	FOOT	185.0	185.0	
* 78001110	PAINT PAVEMENT MARKING-LINE 4"	FOOT	93,575.0	93,575.0	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	426.0	426.0	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	404.0	404.0	
X4060627	LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N50	TON	4,349.0	4,349.0	
X4400196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	5,997.0	5,997.0	
XX006985	SHOULDER EXCAVATION	CU YD	7,035.0	7,035.0	
Z0037320	PAVEMENT PATCHING (PARTIAL DEPTH)	SQ YD	848.0	848.0	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1.0	1.0	
Z0070100	SURVEY MONUMENT COVER ASSEMBLY	EACH	15.0	15.0	

* SPECIALTY ITEMS