

* THICKNESS SHOWN FOR INFORMATION ONLY.

SCHEDULES OF QUANTITIES

HOT-MIX ASPHALT AND HOT-MIX ASPHALT SURFACE REMOVAL (SHEET 2 OF 8)

WESTBOUND PASSING LANE

LOCATION	STA.	TO	STA.	LENGTH (FEET)	WIDTH (FEET)	AREA (SQ YD)	* BINDER THICKNESS (IN)	SURFACE THICKNESS (IN)	BIT. MATLS (PRIME COAT) 40600100 (GALLONS)	AGGREGATE (PRIME COAT) 40600300 (TON)	POLYMERIZED HMA SURFACE COURSE, MIX "C", N105 40603525 (TON)	POLYMERIZED HMA SURFACE COURSE, MIX "D", N105 40603550 (TON)	HMA SURFACE REMOVAL, BUTT JOINT 40600982 (SQ YD)	HMA SURFACE REMOVAL, VAR. DEPTH X4401198 (SQ YD)	HMA SURFACE REMOVAL, 1 1/2" 44000155 (SQ YD)	HMA SURFACE REMOVAL, 13/4" 44000156 (SQ YD)
WBPL	737+00.		737+52.5	52.5	12.0	70.0	1.5	1.75	7.0	0.14	5.88	6.86			70.0	
WBPL	737+52.5		778+85.97	4,133.5	12.0	5,511.3	1.5	1.75	551.1	11.02	462.95	540.11			5,511.3	
WBPL	778+85.97		779+38.47	52.5	12.0	70.0	1.5	1.75	7.0	0.14	5.88	6.86			70.0	
WBPL	779+38.47		781+58.39	219.9												
WBPL	781+58.39		782+10.89	52.5	12.0	70.0	0	1.75	7.0	0.14		6.86	70.00			
WBPL	782+10.89		828+59.25	4,648.4	12.0	6,197.8	0	1.75	619.8	12.40		607.39		6,197.8		
WBPL	828+59.25		829+11.75	52.5	12.0	70.0	0	1.75	7.0	0.14		6.86	70.00			
WBPL	829+11.75		837+66.33	854.6												
WBPL	837+66.33		838+18.83	52.5	12.0	70.0	0	1.75	7.0	0.14		6.86	70.00			
WBPL	838+18.83		905+67.5	6,748.7	12.0	8,998.2	0	1.75	899.8	18.00		881.83		8,998.2		
WBPL	905+67.5		906+20.	52.5	12.0	70.0	0	1.75	7.0	0.14		6.86				70.0
WBPL	906+20.		909+25.	305.0	12.0	406.7	0	1.75	40.7	0.81		39.85				406.7
WBPL	909+25.		909+77.5	52.5	12.0	70.0	0	1.75	7.0	0.14		6.86				70.0
WBPL	909+77.5		1005+74.5	9,597.0	12.0	12,796.0	0	1.75	1,279.6	25.59		1254.01		12,796.0		
WBPL	1005+74.5		1006+27.	52.5	12.0	70.0	0	1.75	7.0	0.14		6.86				70.0
WBPL	1006+27.		1009+32.	305.0	12.0	406.7	0	1.75	40.7	0.81		39.85				406.7
WBPL	1009+32.		1009+84.5	52.5	12.0	70.0	0	1.75	7.0	0.14		6.86				70.0
WBPL	1009+84.5		1037+21.75	2,737.3	12.0	3,649.7	0	1.75	365.0	7.30		357.67		3,649.7		
WBPL	1037+21.75		1037+74.25	52.5	12.0	70.0	0	1.75	7.0	0.14		6.86	70.00			
WBPL	1037+74.25		1040+25.75	251.5												
WBPL	1040+25.75		1040+78.25	52.5	12.0	70.0	0	1.75	7.0	0.14		6.86	70.00			
WBPL	1040+78.25		1088+30.	4,751.8	12.0	6,335.7	0	1.75	633.6	12.67		620.90		6,335.7		
WBPL	1088+30.		1088+82.5	52.5	12.0	70.0	0	1.75	7.0	0.14		6.86				70.0
WBPL	1088+82.5		1091+97.5	315.0	12.0	420.0	0	1.75	42.0	0.84		41.16				420.0
WBPL	1091+97.5		1092+50.	52.5	12.0	70.0	0	1.75	7.0	0.14		6.86				70.0
WBPL	1092+50.		1110+47.5	1,797.5	12.0	2,396.7	0	1.75	239.7	4.79		234.87		2,396.7		
WBPL	1110+47.5		1111+00.	52.5	12.0	70.0	0	1.75	7.0	0.14		6.86	70.00			
WBPL TOTALS =									4,809.9	96.2	474.7	4,713.7	420.0	40,374.0	5,651.3	1,653.3