

SUMMARY OF QUANTITIES (CONT'D)

LOCATION OF WORK:

FAP 741 (IL 105)
 PIATT COUNTY
 STA. 383+70.00
 TO STA. 56+95.70
 RURAL 2-LANE
 80% FEDERAL
 20% STATE
 0040

CONSTRUCTION TYPE CODE:

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1.0
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1.0
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1.0
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1.0
51500100	NAME PLATES	EACH	3.0
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2.0
54001002	BOX CULVERT END SECTIONS, CULVERT NO. 2	EACH	2.0
54001003	BOX CULVERT END SECTIONS, CULVERT NO. 3	EACH	2.0
54001004	BOX CULVERT END SECTIONS, CULVERT NO. 4	EACH	2.0
54020202	PRECAST CONCRETE BOX CULVERTS 2' X 2' (M273)	FOOT	44.0
54020802	PRECAST CONCRETE BOX CULVERTS 8' X 2' (M273)	FOOT	41.0
54020803	PRECAST CONCRETE BOX CULVERTS 8' X 3' (M273)	FOOT	39.0
54021204	PRECAST CONCRETE BOX CULVERTS 12' X 4' (M273)	FOOT	70.0
60250200	CATCH BASINS TO BE ADJUSTED	EACH	1.0
61100605	MISCELLANEOUS CONCRETE	CU YD	0.4
61140600	STORM SEWERS(SPECIAL) 18"	FOOT	92.0
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	2.0
67100100	MOBILIZATION	L SUM	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	24.0
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	261.0
<input type="checkbox"/> Z0010555	DITCH CLEANING	FOOT	400.0
Z0030900	INSPECTION WELLS	EACH	2.0

***SPECIALTY ITEM**
 NON-PARTICIPATING
 100% STATE

FILE NAME =	USER NAME = hennessdm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw_work\pwidot\hennessdm\08184799\05	0800-sht-500.dgn	DRAWN -	REVISED -		741	(8,9,10)CR	PIATT	65	5			
	PLOT SCALE = 40.0000 / IN.	CHECKED -	REVISED -		CONTRACT NO. 70800							
	PLOT DATE = 10/20/2010	DATE -	REVISED -		SCALE:	SHEET NO. 2 OF 3 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			