

# SCHEDULE OF QUANTITIES

**EARTHWORK SCHEDULE**

STATION	(20201200) REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YDS)		(20400800) FURNISHED EXCAVATION (CU YDS)		(Z0010555) DITCH CLEANING (FEET)	
	LI	RI	LI	RI	LI	RI
<b>CULVERT #1</b>						
450+00.00	1.9	2.5	2.4	2.2	0.0	0.0
450+50.00	0.2	0.2	0.1	0.1	0.0	0.0
450+53.00	4.0	3.6	0.3	0.2	0.0	0.0
451+00.00	3.4	3.5	0.3	0.2	0.0	0.0
451+50.00						
<b>SUBTOTAL =</b>	<b>9.5</b>	<b>9.8</b>	<b>3.1</b>	<b>2.7</b>	<b>0.0</b>	<b>0.0</b>
<b>CULVERT #2</b>						
625+50.00	3.7	2.9	1.3	0.8	0.0	0.0
626+00.00	6.6	3.5	1.3	0.8	0.0	0.0
626+50.00	12.4	6.0	0.1	0.2	0.0	0.0
626+78.50	0.0	9.0	0.0	0.2	0.0	0.0
627+00.00	0.0	7.4	0.0	0.1	0.0	0.0
627+33.50						
<b>SUBTOTAL =</b>	<b>22.7</b>	<b>28.8</b>	<b>2.7</b>	<b>2.1</b>	<b>0.0</b>	<b>0.0</b>
<b>CULVERT #3</b>						
835+50.00	0.0	0.0	0.0	0.0	50.0	50.0
836+00.00	7.5	10.5	0.4	0.2	0.0	0.0
836+50.00	4.3	4.7	0.2	0.1	0.0	0.0
836+74.00	4.8	1.7	0.3	5.4	0.0	0.0
837+00.00	7.2	6.0	0.6	10.5	0.0	0.0
837+50.00	0.0	3.8	0.0	0.0	0.0	0.0
838+00.00						
<b>SUBTOTAL =</b>	<b>23.8</b>	<b>26.7</b>	<b>1.5</b>	<b>16.2</b>	<b>50.0</b>	<b>50.0</b>

STATION	(20201200) REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YDS)		(20400800) FURNISHED EXCAVATION (CU YDS)		(Z0010555) DITCH CLEANING (FEET)	
	LI	RI	LI	RI	LI	RI
<b>CULVERT #4</b>						
271+00.00	2.8	2.0	0.0	0.0	0.0	0.0
271+22.00	12.0	12.6	0.1	0.1	0.0	0.0
271+50.00	18.4	26.5	0.2	0.2	0.0	0.0
272+00.00	0.0	10.6	0.0	0.0	50.0	0.0
272+50.00	0.0	0.0	0.0	0.0	0.0	50.0
273+00.00						
<b>SUBTOTAL =</b>	<b>33.2</b>	<b>51.7</b>	<b>0.3</b>	<b>0.3</b>	<b>50.0</b>	<b>50.0</b>
(CH 12)						
45+00.00	N/A	0.0	N/A	0.0	N/A	50.0
45+50.00	N/A	0.0	N/A	0.0	N/A	50.0
46+00.00	N/A	0.0	N/A	0.0	N/A	50.0
46+50.00	N/A	0.0	N/A	0.0	N/A	50.0
47+00.00	N/A	14.1	N/A	5.4	N/A	0.0
48+00.00	N/A	11.2	N/A	6.3	N/A	0.0
48+50.00	N/A	11.6	N/A	14.5	N/A	0.0
49+00.00	N/A	7.1	N/A	10.9	N/A	0.0
49+50.00						
<b>SUBTOTAL =</b>	<b>N/A</b>	<b>44.0</b>	<b>N/A</b>	<b>37.1</b>	<b>N/A</b>	<b>200.0</b>

STATION	(20201200) REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YDS)		(20400800) FURNISHED EXCAVATION (CU YDS)		(Z0010555) DITCH CLEANING (FEET)	
	LI	RI	LI	RI	LI	RI
(IL105 WEST)						
50+50.00	N/A	29.7	N/A	0.0	N/A	0.0
51+00.00	N/A	51.3	N/A	0.0	N/A	0.0
51+50.00	N/A	32.7	N/A	0.0	N/A	0.0
52+00.00	N/A	17.1	N/A	0.0	N/A	0.0
52+50.00	N/A	7.1	N/A	0.0	N/A	0.0
53+00.00	N/A	1.1	N/A	2.3	N/A	0.0
53+50.00	N/A	3.9	N/A	2.4	N/A	0.0
54+00.00	N/A	1.1	N/A	0.0	N/A	0.0
54+14.00						
<b>SUBTOTAL =</b>	<b>N/A</b>	<b>144.1</b>	<b>N/A</b>	<b>4.7</b>	<b>N/A</b>	<b>0.0</b>
<b>GRAND TOTAL =</b>		<b>395.0</b>		<b>71.0</b>		<b>400.0</b>

**EXPLORATION TRENCH, 52" DEPTH (21301052)**

STATION	TO STATION	LENGTH (FT)
<b>(CULVERT #1)</b>		
450+00.00 (LT)	451+00.00 (LT)	100.0
450+00.00 (RT)	451+00.00 (RT)	100.0
<b>(CULVERT #2)</b>		
626+00.00 (LT)	627+00.00 (LT)	100.0
626+00.00 (RT)	627+00.00 (RT)	100.0
<b>(CULVERT #3)</b>		
836+25.00 (LT)	837+25.00 (LT)	100.0
836+25.00 (RT)	837+25.00 (RT)	100.0
<b>(CULVERT #4)</b>		
270+75.00 (LT)	272+25.00 (LT)	150.0
270+75.00 (RT)	272+25.00 (RT)	150.0
<b>TOTAL =</b>		<b>900.0</b>