

SCHEDULE OF QUANTITIES (CONT'D)

CULVERT SCHEDULE

STATION	(20700220) POROUS GRANULAR EMBANKMENT (CU YDS)	(28100201) STONE RIPRAP, CLASS A1 (TONS)	(28100207) STONE RIPRAP, CLASS A4 (TONS)	(28200200) FILTER FABRIC (SQ YDS)	(54001001) BC END SECTIONS, CULVERT NO. 1 (EACH)	(54001002) BC END SECTIONS, CULVERT NO. 2 (EACH)	(54001003) BC END SECTIONS, CULVERT NO. 3 (EACH)	(54001004) BC END SECTIONS, CULVERT NO. 4 (EACH)	(54020202) PCBC 2'x2' (M273) (FEET)	(54020802) PCBC 8'x2' (M273) (FEET)	(54020803) PCBC 8'x3' (M273) (FEET)	(54021204) PCBC 12'x4' (M273) (FEET)
450+53.00	25.1				2.0				44.0			
626+50.00	35.1	19.5				2.0				41.0		
836+74.00	36.1	21.0					2.0				39.0	
271+22.00	146.3	187.1						2.0				70.0
271+22.00 (DS)		25.1	66.7	100.3								
TOTAL =	243.0	253.0	67.0	101.0	2.0	2.0	2.0	2.0	44.0	41.0	39.0	70.0

STORM SEWERS, SPECIAL 18" (61140600)

STATION	TO STATION	FEET
836+44.00 (LT)	836+83.00 (RT)	92.0
TOTAL =		92.0

POROUS GRANULAR EMBANKMENT (20700220) (FOR STORM SEWERS, SPECIAL 18")

STATION	TO STATION	W(FT)	H(FT)	L(FT)	CUYDS
836+60.00 (LT)	836+77.00 (RT)	3.33	1.78	40.0	6.8
TOTAL =					7.0

AGGREGATE SHOULDERS, TYPE B, 6" (48101500)

STATION	TO STATION	LENGTH(FT)	WIDTH(FT)	SQ YDS
(CULVERT #1)				
450+03.00 LT	451+03.00 LT	100.0	3.5	38.9
450+03.00 RT	451+03.00 RT	100.0	3.5	38.9
(CULVERT #2)				
626+00.00 LT	626+81.00 LT	81.0	3.5	31.5
626+00.00 RT	627+00.00 RT	100.0	3.5	38.9
(CULVERT #3)				
836+24.00 LT	837+24.00 LT	100.0	3.5	38.9
836+24.00 RT	837+24.00 RT	100.0	3.5	38.9
(CULVERT #4)				
271+13.00 LT	271+72.00 LT	59.0	3.5	22.9
271+13.00 RT	271+72.00 RT	59.0	3.5	22.9
TOTAL =				272.0

MISCELLANEOUS CONCRETE (61100605)

(CONCRETE COLLAR FOR STORM SEWERS, SPECIAL 18")

STATION	W(FT)	H(FT)	L(FT)	CUYDS
836+44.00 (LT)	2.83	2.83	1.67	0.33
TOTAL =				0.4

NAME PLATES (51500100)

STATION	OFFSET	EACH
626+50.00	22.0' RT	1.0
836+74.00	21.0' RT	1.0
271+22.00	32.5' RT	1.0
TOTAL =		3.0

CATCH BASINS TO BE ADJUSTED (60250200)

STATION	OFFSET	EACH
836+83.63	33.10' RT	1.0
TOTAL =		1.0

PATCHING SCHEDULE

STATION	TO STATION	(44201341) CLASS C PATCHES, TYPE II, 9" (SQ YDS)	(44201345) CLASS C PATCHES, TYPE III, 9" (SQ YDS)	(44201347) CLASS C PATCHES, TYPE IV, 9" (SQ YDS)	(44213100) PAVEMENT FABRIC (SQ YDS)	(44213204) TIE BARS 3/4" (EACH)
450+47.67	450+58.33	29.6				5.0
626+41.33	626+58.67		48.2		48.2	9.0
836+65.33	836+82.67		48.2		48.2	9.0
271+04.73	271+39.27			153.5	153.5	25.0
TOTAL =		30.0	97.0	154.0	250.0	48.0

INSPECTION WELLS (Z0030900)

STATION	OFFSET	EACH
625+98.75	49.5' LT	1.0
272+21.00	59.5' LT	1.0
TOTAL =		2.0