

PAINT PAVEMENT MARKING - LINE

TYP. SEC. *	LOCATION	5"			
		YELLOW			WHITE
		DBL-SOLID	SOLID	SKIP-DASH	SOLID
		(FOOT)	(FOOT)	(FOOT)	(FOOT)
	F. A. P. 733 (IL 61/94)				
(1-3)	STA. 1233+29.50 TO STA. 1242+13.77	1,768.54			1,768.54
	(STA. EON. #1)				
	STA. 1242+13.77 (BK) = STA. 1237+84.46 (AH)				
(4)	STA. 1237+84.46 TO STA. 1244+10.00	1,251.08			
(4)	STA. 1237+84.46 TO STA. 1260+35.75				4,502.58
(4)	STA. 1244+10.00 TO STA. 1256+60.00		1,250.00		
(4)	STA. 1244+10.00 TO STA. 1260+35.75			406.44	
	(BRIDGE OMISSION #1) S. N. 001-0002				
	STA. 1260+35.75 TO STA. 1261+04.25			17.13	137.00
(5)	STA. 1261+04.25 TO STA. 1449+49.65				37,690.80
(5)	STA. 1261+04.25 TO STA. 1449+49.65			4,711.35	
(5)	STA. 1262+45.00 TO STA. 1267+10.00		465.00		
(5)	STA. 1273+25.00 TO STA. 1278+15.00		490.00		
	(STA. EON. #2)				
	STA. 1449+49.65 (BK) = 7+53.50 (AH)				
(6-8)	STA. 7+53.50 TO STA. 130+62.24			3,077.19	24,617.48
	(STA. EON. #3)				
	STA. 130+62.24 (BK) = STA. 134+50.00 (AH)				
(9-11)	STA. 134+50.00 TO STA. 159+40.16			622.54	4,980.32
	(STA. EON. #4)				
	STA. 159+40.16 (BK) = STA. 0+00.94 (AH)				
(12-15)	STA. 0+0.94 TO STA. 60+40.30			1,509.84	12,078.72
	(STA. EON. #5)				
	STA. 60+40.30 (BK) = STA. 59+47.54 (AH)				
(16)	STA. 59+47.54 TO STA. 70+50.52			275.75	2,205.96
	(STA. EON. #6)				
	STA. 70+50.52 (BK) = STA. 70+93.13(AH)				
(17-18)	STA. 70+93.13 TO STA. 123+54.50			1,315.34	10,522.74
	(BRIDGE OMISSION #2) S. N. 034-0065				
	STA. 123+54.50 TO STA. 125+00.00			36.38	291
(19)	STA. 125+00.00 TO STA. 179+40.00			1,360.00	
(19-23)	STA. 125+00.00 TO STA. 197+32.00				14,464
(19-23)	STA. 179+40.00 TO STA. 197+32.00	3,584.00			
	SUBTOTAL	6,603.62	2,205.00	13,331.94	113,259.14
	PROJECT TOTAL		135,400		

FILE NAME =	USER NAME = coxjm	DESIGNED - JWC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES					F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\pwidot\coxjm\d0215198\d672880	5ht-Sch.dgn	DRAWN - JWC	REVISED -		733	IRS-3, 7RS-5	.	48	13					
	PLOT SCALE = 100.0000 ' / IN.	CHECKED - RSC	REVISED -		CONTRACT NO. 72880									
	PLOT DATE = Sep-08-2010 10:42:21AM	DATE -	REVISED -		SCALE:	SHEET NO. 5 OF 7 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT					