

**PAVEMENT SCHEDULE**

TYP SEC #	LOCATION				LENGTH FOOT	PAVEMENT WIDTH FOOT	LEVELING BINDER THICKNESS INCH	HMA SURF THICKNESS INCH	HMA SURF REM BUTT JOINT SQ YD	HMA SURF REMOVAL VAR DP SQ YD	HMA SURF REMOVAL 1 1/2" SQ YD	HMA SURF REMOVAL 2 1/4" SQ YD	HMA CONC SURF CSE "C" N50 TON	LEV BINDER (MM), N50 TON	BIT MAT PRIME COAT TON	AGG PRIME COAT TON
	STATION TO STATION															
	F. A. P. 733 (IL 61/94) (cont.)				-	-	-	-	-	-	-	-	-	-	-	-
(18)	STA. 123+54.50	TO	STA. 123+94.50	RT	40.00	4	-	-	-	-	17.78	-	-	-	0.01	0.04
	(BRIDGE OMISSION #2) STA. 123+54.50 TO STA. 125+00.00															
(19)	STA. 124+92.00	TO	STA. 125+00.00	RT	8.00	4	-	-	-	-	3.56	-	-	-	0.001	0.01
(19)	STA. 125+00.00	TO	STA. 125+20.00		20.00	30	-	-	66.67	-	-	-	-	-	0.03	0.13
(19-23)	STA. 125+00.00	TO	STA. 197+32.00		7,232.00	26	-	1.5	-	-	-	-	1,754.97	-	-	-
(19)	STA. 125+20.00	TO	STA. 125+35.00		15.00	26	0 to 0.75	-	-	-	-	-	-	0.91	-	-
(19)	STA. 125+20.00	TO	STA. 127+17.00		197.00	30	-	-	-	656.67	-	-	-	-	0.25	1.31
(19-23)	STA. 125+35.00	TO	STA. 196+97.00		7,162.00	26	0.75	-	-	-	-	-	-	868.99	-	-
(19-23)	STA. 127+17.00	TO	STA. 197+12.00		6,995.00	26	-	-	-	20,207.78	-	-	-	-	7.68	40.42
(23)	STA. 196+97.00	TO	STA. 197+12.00		15.00	26	0.75 to 0	-	-	-	-	-	-	0.91	-	-
(23)	STA. 197+12.00	TO	STA. 197+32.00		20.00	26	-	-	57.78	-	-	-	-	-	0.02	0.12
	INCIDENTAL HMA SURF. (ENTR & SIDE RDS)				-	-	-	-	2,890.17	-	-	-	-	-	4.12	5.78
	SUBTOTAL								3,014.61	20,864.44	21.33	0.00	1,754.97	870.81	12.10	47.80
	PROJECT TOTAL								3,260	132,115	2,926	376	13,691	5,531	56	278