ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

					LOCATION OF WORK	CONSTRUCTION TYPE CODE			
	CODE NO.	ITEM		UNIT	80% FED. 20% STATE TOTAL QUANTITY	ROADWAY 0004	STRUCTURE 0011		
	50400735	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS 63"		FOOT	793.5		793.5		
	50800205	REINFORCEMENT BARS, EPOXY COATED		POUND	71,770		71,770		
	50800515	BAR SPLICERS		EACH	674		674		
	51201900	FURNISHING STEEL PILES HP14X89		FOOT	186		186		
	51500100	NAME PLATES		EACH	1		1		
	542A5479	PIPE CULVERTS, CLASS A, TYPE 1	EQUIVALENT ROUND-SIZE 24"	FOOT	48	48			
	54214509	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 24"		EACH	2	2			
*	54215547	METAL END SECTIONS 12"		EACH	2	2			
	59100100	GEOCOMPOSITE WALL DRAIN		SQ YD	78		78		
	60105000	PIPE DRAINS, CORRUGATED STEEL OR ALUMINUM ALLOY 12"		FOOT	24	24			
*	Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"		FOOT	165		165		
	60900215	TYPE C INLET BOX, STANDARD 609001		EACH	2	2			
**	63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS		FOOT	362.5	362.5			
**	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6		EACH	3	3			

* INDICATES SPECIAL REQUIRED

** Specialty Items

Rev.

FILE NAME = c:\pw_work\pwidot\laughlinrl\d0230976\B007SUM01.SHT	USER NAME = laughlinrl	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 20.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = Aug-11-2010 10:31:09AM	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
506	123 B-1	HANCOCK	70	6
		CONTRACT NO. 72992		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		