

LEVELING BINDER SCHEDULE						
STATION	TO	STATION	AVERAGE END AREA	DISTANCE	VOLUME	40600625 LEVELING BINDER (MACHINE METHOD), N50
			(SQ FT)	(FEET)	(CU FT)	(TON)
34+00		35+00	1.5	100.0	150.0	11.2
35+00		35+89.94	1.5	89.9	134.9	10.1
RAILROAD OMISSION						
36+17.08		37+00	1.5	82.9	124.4	9.3
37+00		37+36	1.5	36.0	54.4	4.1
BRIDGE OMISSION						
39+23		40+00	5.5	77.0	423.5	31.7
40+00		41+00	3.25	100.0	325.0	24.3
41+00		42+00	1.5	100.0	150.0	11.2
42+00		42+40	1.5	40.0	60.0	4.5
TOTALS						106.4
USE						107

BUTT JOINT / RAMP SCHEDULE						
STATION	TO	STATION	PAVEMENT WIDTH	DISTANCE	40600982 HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	40600990 TEMPORARY RAMP
			(FEET)	(FEET)	(SQ YD)	(SQ YD)
34+00		34+26	25	5	73	14
35+63.94		35+89.94	24	5	70	14
RAILROAD OMISSION						
36+17.08		36+43.08	24	5	70	14
BRIDGE OMISSION						
42+14		42+40	25.4	5	74	15
TOTALS					287	57

AGGREGATE SHOULDER SCHEDULE						
STATION	TO	STATION	LT/RT	WIDTH	THICKNESS	48101200 AGGREGATE SHOULDERS, TYPE B
				(FEET)	(FEET)	(TON)
35+00		35+17	LT	4	0.5	3
35+84		35+99	LT	4	0.5	3
36+24		36+43	LT	4	0.5	3
36+85		37+72	LT	4	0.5	14
38+87		42+40	LT	4	0.5	54
34+77		35+82	RT	4	0.5	16
36+09		36+19	RT	4	0.5	2
36+64		37+72	RT	4	0.5	17
38+87		41+42	RT	4	0.5	39
41+82		42+40	RT	4	0.5	9
TOTALS						160

HMA SHOULDER SCHEDULE							
STATION	TO	STATION	LT/RT	BITUMINOUS SHOULDER WIDTH	35600716 HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	48203100 HOT-MIX ASPHALT SHOULDERS	48203029 HOT-MIX ASPHALT SHOULDERS, 8"
				(FEET)	(SQ YD)	(TON)	(SQ YD)
34+00		35+00	LT	5.6		7.9	
35+00		35+96	LT	6.0			64.0
34+00		34+78	RT	5.7		6.3	
34+78		35+84	RT	6.0			70.7
RAIL ROAD OMISSION							
36+24		37+27	LT	6.0		8.7	
36+24		37+76	LT	6.0	102		
36+10		37+27	RT	6.0		9.9	
36+10		37+76	RT	6.0	111		
BRIDGE OMISSION							
38+61		41+90	LT	6.0	220		
39+17		41+90	LT	6.0		23.0	
41+90		42+40	LT	5.0			27.8
38+61		41+40	RT	6.0	186		
39+17		41+40	RT	6.0		18.8	
41+86		42+40	RT	4.4			26.4
TOTALS					619	74.6	188.9
USE					619	75	189

FILE NAME =	USER NAME = laughl1nr1	DESIGNED -	REVISED -
et:\pwork\pwork\laughl1nr1\0230976\8077SCH01.SHT		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
506	123 B-1	HANCOCK	70	14
CONTRACT NO. 72992				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				