

SUMMARY OF QUANTITIES

CODE NO.	ITEM	SP. PROV.	UNIT	80% FED. 20% STATE TOTAL QUANTITIES	80% FEDERAL 20% STATE CONSTRUCTION TYPE CODE			
					0005 ROADWAY	0011 STRUCTURE		
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70		TON	4251	4251			
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING		TON	32	32			
44000100	PAVEMENT REMOVAL	*	SO YD	254	254			
44000400	GUTTER REMOVAL		FOOT	20	20			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"		SO YD	5027	5027			
44004250	PAVED SHOULDER REMOVAL		SO YD	36	36			
44200176	PAVEMENT PATCHING, TYPE I, 15 INCH		SO YD	25	25			
44200180	PAVEMENT PATCHING, TYPE II, 15 INCH		SO YD	350	350			
44200184	PAVEMENT PATCHING, TYPE III, 15 INCH		SO YD	365	365			
44200186	PAVEMENT PATCHING, TYPE IV, 15 INCH		SO YD	665	665			
48101200	AGGREGATE SHOULDERS, TYPE B		TON	1644	1644			
48203029	HOT-MIX ASPHALT SHOULDERS, 8"		SO YD	1328	1328			
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	*	EACH	1		1		
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	*	EACH	1	1			
50104400	CONCRETE HEADWALL REMOVAL		EACH	1	1			
50105220	PIPE CULVERT REMOVAL	*	FOOT	133	133			
50200100	STRUCTURE EXCAVATION		CU YD	312		312		
50300100	FLOOR DRAINS		EACH	12		12		
50300225	CONCRETE STRUCTURES		CU YD	63.2		63.2		
50300255	CONCRETE SUPERSTRUCTURE		CU YD	283.0		283.0		
50300260	BRIDGE DECK GROOVING		SO YD	620		620		
50300280	CONCRETE ENCASEMENT		CU YD	5.6		5.6		
50300300	PROTECTIVE COAT		SO YD	777		777		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL		L SUM	1		1		
50500505	STUD SHEAR CONNECTORS		EACH	1998		1998		
50800105	REINFORCEMENT BARS		POUND	3210	3210			
50800205	REINFORCEMENT BARS, EPOXY COATED		POUND	71240		71240		
50800515	BAR SPLICERS		EACH	663		663		
51201610	FURNISHING STEEL PILES HP12X63		FOOT	805		805		
51202305	DRIVING PILES		FOOT	805		805		