

SUMMARY OF QUANTITIES

CODE NO.	ITEM	SP. PROV.	UNIT	80% FED. 20% STATE TOTAL QUANTITIES	80% FEDERAL 20% STATE CONSTRUCTION TYPE CODE			
					0005 ROADWAY	0011 STRUCTURE		
51203610	TEST PILE STEEL HP12X63		EACH	2		2		
51500100	NAME PLATES		EACH	1		1		
52100520	ANCHOR BOLTS, 1"		EACH	24		24		
54002020	EXPANSION BOLTS 3/4 INCH		EACH	68	68			
54003000	CONCRETE BOX CULVERTS		CU YD	23.0	23.0			
542A0235	PIPE CULVERTS, CLASS A, TYPE 1 30"		FOOT	134	134			
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"		FOOT	30	30			
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"		EACH	5	5			
54215550	METAL END SECTIONS 15"		EACH	2	2			
54215553	METAL END SECTIONS 18"		EACH	1	1			
54248510	CONCRETE COLLAR		CU YD	2.3	2.3			
59100100	GEOCOMPOSITE WALL DRAIN		SO YD	83		83		
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS		EACH	4	4			
60219400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 12 FRAME AND GRATE		EACH	1	1			
60222100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 12 FRAME AND GRATE		EACH	1	1			
60500060	REMOVING INLETS		EACH	2	2			
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS		FOOT	2550	2550			
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6		EACH	4	4			
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT		EACH	17	17			
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED		EACH	1	1			
63200310	GUARDRAIL REMOVAL		FOOT	3099	3099			
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS		EACH	12	12			
67000400	ENGINEER'S FIELD OFFICE, TYPE A		CAL MO	9	9			
67100100	MOBILIZATION		L SUM	1	1			
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201		L SUM	1	1			
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306		L SUM	1	1			
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326		L SUM	1	1			
70103815	TRAFFIC CONTROL SURVEILLANCE		CAL DA	10	10			
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS		EACH	1	1			
70300100	SHORT TERM PAVEMENT MARKING		FOOT	4776	4776			

*Specialty Items

FILE NAME =	USER NAME = laughlin	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\puidot\laughlin\1\0244977.DWG	2805-shr-Summary.dgn	DRAWN -	REVISED -			685	1117,1181RS-4,119RS-1; 118B-1	HANCOCK	101	5	
	PLOT SCALE = 1/8"=1'-0"	CHECKED -	REVISED -			SCALE: none SHEET NO. 3 OF 4 SHEETS STA. TO STA.		CONTRACT NO. 72B05			
	PLOT DATE = Nov-03-2010 10:14:48AM	DATE -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					