

PAVEMENT REMOVAL

44000100

STATION TO STATION	SIDE	WIDTH	SQ YD
FAP 685 (IL 9)			
1218+80	1219+22	LT & RT	18-26
1219+84	1220+28	LT & RT	18-26
TOTAL			207.6
USE			208

PAVED SHOULDER REMOVAL

44004250

STATION TO STATION	SIDE	WIDTH	SQ YD
FAP 685 (IL 9)			
1218+56.8	1218+86.8	RT	2.0
1218+61.8	1219+11.8	LT	2.0
1219+93.7	1220+44.8	RT	2.0
1220+19.5	1220+49.5	LT	2.0
TOTAL			35.6
USE			36

REMOVAL OF EXSTING PRECAST CONCRETE UNITS

X0324744

STATION TO STATION	SIDE	WIDTH	SO FT
FAP 685 (IL 9)			
1218+86.8	1219+14.8	RT	7.5
1219+11.3	1219+29.3	LT	7.5
1219+77.0	1219+94.9	RT	7.5
1219+91.6	1220+19.5	LT	7.5
TOTAL			687.9
USE			688

REMOVAL OF EXISTING STRUCTURES

PAY ITEM NO.	STATION	SIDE	DESCRIPTION	EACH
FAP 685 (IL 9)				
50100300	1219+54	LT & RT	S.N. 034-0008	1
50100400	1246+60	RT	2'x2' BOX CULVERT WITH HEADWALLS	1

PIPE CULVERT REMOVAL

50105220

STATION	SIDE	DESCRIPTION	FOOT
FAP 685 (IL 9)			
1188+15	RT	30" CLAY	100
1222+40	LT	15" CLAY/12" CMP	33
TOTAL			133

GUTTER REMOVAL

44000400

STATION TO STATION	SIDE	FOOT
FAP 685 (IL 9)		
1182+95	1183+05	RT
1182+95	1183+05	LT
TOTAL		20

NOTE: THIS IS AN ESTIMATED QUANTITY.

CONCRETE HEADWALL REMOVAL

50104400

STATION	SIDE	EACH
FAP 685 (IL 9)		
1247+85	LT	1
TOTAL		1

REMOVING INLETS

60500060

STATION	SIDE	EACH
FAP 685 (IL 9)		
1183+00	RT	1
1183+00	LT	1
TOTAL		2

GUARDRAIL REMOVAL

63200310

STATION TO STATION	SIDE	FOOT
FAP 685 (IL 9)		
1150+79	1152+34	RT
1151+78	1153+30	LT
1171+28	1173+82	LT
1190+02	1200+88	RT
1193+20	1194+26	LT
1207+14	1209+19	LT
1207+24	1209+29	RT
1225+66	1232+46	RT
1232+07	1234+63	LT
TOTAL		3099

PAVEMENT MARKING REMOVAL

78300100

STATION TO STATION	SIDE	DESCRIPTION	SO FT
FAP 510 9IL 96)			
1215+00	1221+50	CL	SKIP-DASH
1215+00	1217+00	LT CL	NO-PASSING
1221+50	1224+00	LT CL	NO-PASSING
1221+50	1224+00	RT CL	NO-PASSING
1216+56	1222+40	LT	EDGE LINE
1216+60	1218+00	RT	EDGE LINE
1221+00	1222+44	RT	EDGE LINE
TOTAL			792.5
USE			793