

## SUMMARY OF QUANTITIES

LOCATION OF WORK				IL 104 80% FED / 20% STATE ROADWAY	IL 104 80% FED / 20% STATE STRUCTURE
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE
CODE NO.	ITEM	UNITS	TOTAL QUANTITY	0004	0011
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1,093	1,093	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	809	809	
20200100	EARTH EXCAVATION	CU YD	5,041	5,041	
20200500	EARTH EXCAVATION (WIDENING)	CU YD	785	785	
20300100	CHANNEL EXCAVATION	CU YD	2,056	2,056	
X2070304	POROUS GRANULAR EMBANKMENT, <i>SPECIAL</i>	CU YD	162		162
25000200	SEEDING, CLASS 2	ACRE	3.8	3.8	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	342	342	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	342	342	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	342	342	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	7.6	7.6	
25100115	MULCH, METHOD 2	ACRE	3.8	3.8	
25100830	EROSION CONTROL BLANKET	SQ YD	206	206	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	380	380	
28000315	AGGREGATE DITCH CHECKS	TON	70	70	
28000400	PERIMETER EROSION BARRIER	FOOT	1856	1856	
28000500	INLET AND PIPE PROTECTION	EACH	1	1	
28100207	STONE RIPRAP, CLASS A4	TON	2905	2905	
28200200	FILTER FABRIC	SQ YD	4355	4355	
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	1,822	1,822	
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	67	67	
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	1,455	1,455	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.8	1.8	
40600300	AGGREGATE (PRIME COAT)	TON	8.6	8.6	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	152	152	

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
et:\pwork\pwork\laughlinr1\0215213\d072b98-shr-soq.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**IL 104 OVER GRINDSTONE CREEK  
SUMMARY OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
745	107B-1	ADAMS	86	3
CONTRACT NO. 72B98			ILLINOIS FED. AID PROJECT	

*Rev.*