

| SHORT-TERM PAVEMENT MARKING          |                |    |                |                                       |                                     |                       |                |                                     |                     | FOOT        |                                     |
|--------------------------------------|----------------|----|----------------|---------------------------------------|-------------------------------------|-----------------------|----------------|-------------------------------------|---------------------|-------------|-------------------------------------|
| TEMPORARY PAVEMENT MARKING - LINE 5" |                |    |                |                                       |                                     |                       |                |                                     |                     | FOOT        |                                     |
| WORK ZONE PAVEMENT MARKING REMOVAL   |                |    |                |                                       |                                     |                       |                |                                     |                     | SQ FT       |                                     |
| PAINT PAVEMENT MARKING - LINE 5"     |                |    |                |                                       |                                     |                       |                |                                     |                     | FOOT        |                                     |
| PAVEMENT MARKING REMOVAL             |                |    |                |                                       |                                     |                       |                |                                     |                     | SQ FT       |                                     |
| LOCATION                             | STATION        | TO | STATION        | SHORT TERM<br>PVMT. MARKING<br>(FOOT) | TEMP. PVMT.<br>MARKING 5"<br>(FOOT) | WZ PVMT. MARKING REM. |                | PAINT PVMT.<br>MARKING 5"<br>(FOOT) | PVMT. MARK. REMOVAL |             | REMARKS                             |
|                                      |                |    |                |                                       |                                     | (FOOT)                | (SQ FT)        |                                     | (FOOT)              | (SQ FT)     |                                     |
| IL 104                               | LT. 1239+50.00 | TO | LT. 1253+50.00 | 224.0                                 |                                     | 56.0                  | 23.3           |                                     |                     |             | STAGE V EDGELINE (4 APPLICATIONS)   |
| IL 104                               | 1239+50.00     | TO | 1253+50.00     | 560.0                                 |                                     | 140.0                 | 58.3           |                                     |                     |             | STAGE V CENTERLINE (4 APPLICATIONS) |
| IL 104                               | RT. 1239+50.00 | TO | RT. 1253+50.00 | 224.0                                 |                                     | 56.0                  | 23.3           |                                     |                     |             | STAGE V EDGELINE (4 APPLICATIONS)   |
| IL 104                               | LT. 1239+50.00 | TO | LT. 1253+50.00 |                                       | 1,400.0                             |                       |                | 1,400.0                             |                     |             |                                     |
| IL 104                               | 1239+50.00     | TO | 1253+50.00     |                                       | 350.0                               |                       |                | 350.0                               |                     |             |                                     |
| IL 104                               | RT. 1239+50.00 | TO | RT. 1253+50.00 |                                       | 1,400.0                             |                       |                | 1,400.0                             |                     |             |                                     |
| IL 104                               | LT. 1242+65.00 | TO | LT. 1250+55.00 |                                       |                                     | 790.0                 | 329.2          |                                     |                     |             | STAGE II                            |
| IL 104                               | RT. 1242+65.00 | TO | LT. 1244+42.70 |                                       |                                     | 165.0                 | 68.8           |                                     |                     |             | STAGE II                            |
| IL 104                               | LT. 1244+42.70 | TO | LT. 1248+45.23 |                                       |                                     | 402.5                 | 167.7          |                                     |                     |             | STAGE II                            |
| IL 104                               | LT. 1248+45.23 | TO | RT. 1250+55.00 |                                       |                                     | 225.0                 | 93.8           |                                     |                     |             | STAGE II                            |
| IL 104                               | LT. 1242+65.00 | TO | RT. 1244+51.60 |                                       |                                     | 188.0                 | 78.3           |                                     |                     |             | STAGE III                           |
| IL 104                               | RT. 1244+51.60 | TO | RT. 1248+58.00 |                                       |                                     | 406.5                 | 169.4          |                                     |                     |             | STAGE III                           |
| IL 104                               | RT. 1248+58.00 | TO | LT. 1250+55.00 |                                       |                                     | 205.0                 | 85.4           |                                     |                     |             | STAGE III                           |
| IL 104                               | RT. 1242+65.00 | TO | RT. 1250+55.00 |                                       |                                     | 790.0                 | 329.2          |                                     |                     |             | STAGE III                           |
| IL 104                               | 1242+65.00     | TO | 1244+00.00     |                                       |                                     |                       |                | 135.0                               | 14.1                |             | STAGE III                           |
| IL 104                               | 1246+37.40     | TO | 1247+31.00     |                                       |                                     |                       |                | 93.6                                | 39.0                |             | STAGE III                           |
| IL 104                               | 1249+00.00     | TO | 1250+55.00     |                                       |                                     |                       |                | 155.0                               | 16.1                |             | STAGE III                           |
| <b>TOTAL</b>                         |                |    |                | <b>1,008.0</b>                        | <b>3,150.0</b>                      |                       | <b>1,426.7</b> | <b>3,150.0</b>                      |                     | <b>69.2</b> |                                     |

| FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS |         |        |  | EACH        |
|--|---------|--------|--|-------------|
| STATION                                      | RT / LT | OFFSET |  | EACH        |
| 1242+00.00                                   | LT      | 40.0   |  | 1.0         |
| 1242+00.00                                   | LT      | 75.0   |  | 1.0         |
| 1245+95.00                                   | LT      | 90.0   |  | 1.0         |
| 1246+21.51                                   | LT      | 118.0  |  | 1.0         |
| 1247+22.50                                   | LT      | 118.0  |  | 1.0         |
| 1247+40.00                                   | LT      | 90.0   |  | 1.0         |
| 1254+00.00                                   | LT      | 60.0   |  | 1.0         |
| 1242+25.00                                   | RT      | 40.0   |  | 1.0         |
| 1246+22.73                                   | RT      | 105.0  |  | 1.0         |
| 1246+22.84                                   | RT      | 122.0  |  | 1.0         |
| 1248+25.00                                   | RT      | 122.0  |  | 1.0         |
| 1248+25.00                                   | RT      | 85.0   |  | 1.0         |
| 1252+00.00                                   | RT      | 50.0   |  | 1.0         |
| <b>TOTAL</b>                                 |         |        |  | <b>13.0</b> |

| TEMPORARY CONCRETE BARRIER   |                |    |                |                                  |                                  |                                  |                                       |                                |                                     |           | FOOT |
|--|----------------|----|----------------|----------------------------------|----------------------------------|----------------------------------|---------------------------------------|--------------------------------|-------------------------------------|-----------|------|
| RELOCATE TEMPORARY CONCRETE BARRIER                                    |                |    |                |                                  |                                  |                                  |                                       |                                |                                     |           | FOOT |
| RAISED REFLECTIVE PAVEMENT MARKER                                      |                |    |                |                                  |                                  |                                  |                                       |                                |                                     |           | EACH |
| RAISED REFLECTIVE PAVEMENT MARKER REMOVAL                              |                |    |                |                                  |                                  |                                  |                                       |                                |                                     |           | EACH |
| IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW) TEST LEVEL 3 |                |    |                |                                  |                                  |                                  |                                       |                                |                                     |           | EACH |
| IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW) TEST LEVEL 3  |                |    |                |                                  |                                  |                                  |                                       |                                |                                     |           | EACH |
| LOCATION   | STATION        | TO | STATION        | TEMP. CONC.<br>BARRIER<br>(FOOT) | RELOCATE<br>TEMP. BAR.<br>(FOOT) | RAISED<br>PVMT. MARKER<br>(EACH) | RAISED PVMT.<br>MARKER REM.<br>(EACH) | IMPACT<br>ATTENUATOR<br>(EACH) | REL. IMPACT<br>ATTENUATOR<br>(EACH) | REMARKS   |      |
| IL 104   | RT. 1244+71.00 | TO | LT. 1245+83.00 | 108.0                            |                                  |                                  |                                       |                                |                                     | STAGE II  |      |
| IL 104   | LT. 1245+81.00 | TO | LT. 1247+85.00 | 204.0                            |                                  |                                  |                                       |                                |                                     | STAGE II  |      |
| IL 104   | LT. 1247+83.00 | TO | RT. 1248+95.50 | 108.0                            |                                  |                                  |                                       |                                |                                     | STAGE II  |      |
| IL 104   | LT. 1244+71.00 | TO | RT. 1245+83.00 |                                  | 108.0                            |                                  |                                       |                                |                                     | STAGE III |      |
| IL 104   | RT. 1245+81.00 | TO | RT. 1247+85.00 |                                  | 204.0                            |                                  |                                       |                                |                                     | STAGE III |      |
| IL 104   | RT. 1247+83.00 | TO | LT. 1248+95.50 |                                  | 108.0                            |                                  |                                       |                                |                                     | STAGE III |      |
| IL 104   | 1239+50.00     | TO | 1253+50.00     |                                  |                                  | 16.0                             | 18.0                                  |                                |                                     | STAGE II  |      |
| IL 104   |                |    | RT. 1244+71.00 |                                  |                                  |                                  |                                       | 1.0                            |                                     | STAGE III |      |
| IL 104   |                |    | RT. 1248+95.50 |                                  |                                  |                                  |                                       | 1.0                            |                                     | STAGE III |      |
| IL 104   |                |    | LT. 1244+71.00 |                                  |                                  |                                  |                                       |                                | 1.0                                 | STAGE III |      |
| IL 104   |                |    | LT. 1248+95.50 |                                  |                                  |                                  |                                       |                                | 1.0                                 | STAGE III |      |
| <b>TOTAL</b>   |                |    |                | <b>420.0</b>                     | <b>420.0</b>                     | <b>16.0</b>                      | <b>18.0</b>                           | <b>2.0</b>                     | <b>2.0</b>                          |           |      |