

**EARTH EXCAVATION (WIDENING) SCHEDULE**

LOCATION		20200500 VOLUME (CU YD)	
FAP 751 (IL 96) - SN 075-0004	22+190.00 TO 22+273.75	LT	11.6
		RT	11.6
	22+321.93 TO 22+405.00	LT	11.5
		RT	11.5
<b>TOTAL</b>			<b>46</b>

**PAVING SCHEDULE**

LOCATION		35600712 HMA BASE COURSE WIDENING 9" (SQ YD)	40600200 BITUMINOUS MATERIALS (PRIME COAT) (TON)	40600300 AGGREGATE (PRIME COAT) (TON)	40600625 LEVELING BINDER (MM), N50 (TON)	40603310 HMA SURFACE COURSE, MIX C, N50 (TON)	44000155 HMA SURFACE REMOVAL 1 1/2" (TON)
FAP 751 (IL 96) - SN 075-0024	294+17.00 TO 295+75.36	LT	0.13	0.66	16.2	27.8	331.3
		RT	0.13	0.69	16.9	29.0	345.8
	296+64.45 TO 298+15.00	LT	0.12	0.62	15.2	26.0	309.3
		RT	0.12	0.64	15.8	27.0	321.6
FAP 751 (IL 96) - SN 075-0004	22+190.00 TO 22+273.75	LT	46.5	0.06	0.30	11.5	149.8
		RT	46.5	0.06	0.30	11.5	149.8
	22+321.93 TO 22+405.00	LT	46.1	0.06	0.30	11.4	148.6
		RT	46.1	0.06	0.30	11.4	148.6
<b>TOTAL</b>			<b>185</b>	<b>0.7</b>	<b>4</b>	<b>64</b>	<b>1905</b>

**TEMPORARY RAMP SCHEDULE**

LOCATION		40600990 AREA (SQ YD)
FAP 751 (IL 96) - SN 075-0024	294+17.00	17.8
	295+75.36	48.2
	296+64.45	48.2
FAP 751 (IL 96) - SN 075-0004	298+15.00	13.4
	221+90.00	17.8
	222+74.25	14.9
	223+21.43	14.9
	224+05.00	17.8
<b>TOTAL</b>		<b>193</b>

**SHORT-TERM PAVEMENT MARKING SCHEDULE**

LOCATION		70300100 LENGTH (FOOT)		
FAP 751 (IL 96) - SN 075-0024	294+17.00 TO 298+15.00	CENTERLINE	3	120
		EDGE LINE	3	96
FAP 751 (IL 96) - SN 075-0004	221+90.00 TO 224+05.00	CENTERLINE	2	48
		EDGE LINE	2	48
<b>TOTAL</b>				<b>312</b>

**PAVEMENT MARKING SCHEDULE**

LOCATION		70300230 TEMPORARY 5" (FOOT)	78001120 PAINT 5" (FOOT)	78100100 RAISED REFL MKR (EACH)
FAP 751 (IL 96) - SN 075-0024	293+42 TO 299+03	CENTERLINE	YELLOW SKIP DASH	150
	294+17 TO 298+15	RT EDGE LINE	WHITE SOLID	398
	294+17 TO 298+15	LT EDGE LINE	WHITE SOLID	398
FAP 751 (IL 96) - SN 075-0004	220+37 TO 225+58	CENTERLINE	YELLOW SKIP DASH	140
	221+90 TO 224+05	LT EDGE LINE	WHITE SOLID	215
	221+90 TO 224+05	RT EDGE LINE	WHITE SOLID	215
<b>TOTAL</b>				<b>1516</b>