

Work Zone Pavement Marking Removal

Location	Start Station	End Station	Length (FOOT)	Quantity (FOOT)	
				Center Skip Dash	Shoulder 4'
Andrew Road	1074+47.	1076+19.1	172.10	17	3.442
	1075+08.4	1121+40.34	4631.94	463	92.6388
	1+00.	5+60.23	460.23	46	9.2046
<i>Andrew Rd Subtotal</i>			5264.27	526	105
IL 124	276+34.	368+98.9	9264.90	926	185.298
	368+98.99	395+85.96	2686.97	269	53.7394
	396+39.54	420+32.31	2392.77	239	47.8554
	420+49.79	464+33.95	4384.16	438	87.6832
	465+00.	522+50.	5750.00	575	115
<i>IL 24 Subtotal</i>			24478.80	2448	490
Total			29743	2974	595

Grading, Shaping, and Seeding Foreslope

Location	Station to Station		Length (FOOT)	Quantity (Unit)
Andrew Road	1085+40.	1121+40.34	3600.34	72.01
	1+00.	5+60.23	460.23	9.20
<i>Andrew Rd Subtotal</i>			4060.57	81.21
IL 124	276+34.	368+98.9	9264.90	185.30
	368+98.99	395+85.96	2686.97	53.74
	396+39.54	420+32.31	2392.77	47.86
	420+49.79	464+33.95	4384.16	87.68
	465+00.	522+50.	5750.00	115.00
<i>IL 24 Subtotal</i>			24478.80	489.58
Total			28539	571