

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNITS	TOTAL QUANT	URBAN			
				90% FED, 5% STATE 5% CITY		90% FED, 10% STATE 5% CITY	
				IL 16 & CORV. LN.	IL 16 & OHREN LN.	IL 16 & OLD US 66	IL 16 & SHRMMN ST.
CONSTRUCTION TYPE CODE							
				0021	0021	0021	0021
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SO FT	233			233	
67100100	MOBILIZATION	L SUM	1	0.25	0.25	0.25	0.25
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1	0.25	0.25	0.25	0.25
72400710	RELOCATE SIGN PANEL, TYPE 1	SO FT	18			18	
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	36			36	
81500120	GULFBOX JUNCTION, COMPOSITE CONCRETE	EACH	1			1	
81500130	GULFBOX JUNCTION REMOVAL	EACH	1			1	
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	36			36	
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	2	1			1
86200200	UNINTERRUPTIBLE POWER SUPPLY, STANDARD	EACH	4	1	1	1	1
86400100	TRANSCEIVER - FIBER OPTIC	EACH	5	1	1	2	1
87100110	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 6F	FOOT	5,117	992	1,399	2,627	99
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	612	22	24	542	24
87502690	TRAFFIC SIGNAL POST, ALUMINUM 15 FT.	EACH	1	1			
87502700	TRAFFIC SIGNAL POST, ALUMINUM 16 FT.	EACH	2			2	
87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	2			2	
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6			6	
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	26			26	
87900200	DRILL EXISTING HANDHOLE	EACH	2			2	
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2			2	
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	13	3	2	6	2
88040120	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	2				2
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	5	1		2	2
88040250	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3 SECTION, 1-4 SECTION, BRACKET MOUNTED	EACH	1	1			

* - SEE SPECIAL PROVISIONS