

S U M M A R Y O F Q U A N T I T I E S

CODE NO.	ITEM	UNIT	100% STATE
			TOTAL QTY
20200100	EARTH EXCAVATION	CU YD	88.5
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	8.2
40600300	AGGREGATE (PRIME COAT)	TON	43.3
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600990	TEMPORARY RAMP	SQ YD	81
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX ^c , N50	TON	2,424
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	21,643
44200180	PAVEMENT PATCHING, TYPE II, 15 INCH	SQ YD	100
44200184	PAVEMENT PATCHING, TYPE III, 15 INCH	SQ YD	100
44200186	PAVEMENT PATCHING, TYPE IV, 15 INCH	SQ YD	500
44213200	SAW CUTS	FOOT	615
48101200	AGGREGATE SHOULDERS, TYPE B	TON	170
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	137
50105220	PIPE CULVERT REMOVAL	FOOT	30
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	12.7

QUANTITIES
SBI 96 (WARSAW SPUR)
SECTION 123 RS-6
HANCOCK COUNTY