

SUMMARY OF QUANTITIES			90% FED./10% STATE	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CLAY COUNTY	EFFINGHAM COUNTY	
				0004	0004	0014
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1		1	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1		1	
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1		1	
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1		1	
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1		1	
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1		1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10		10	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7595	306	7289	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	84860	3726	81134	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2229	102	2127	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	6600	875	5725	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	6425	875	5550	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	93.6		93.6	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	22300		22300	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	500		500	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	80		80	
* 78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	59164	3301	55863	
* 78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	7690	425	7265	
* 78004240	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 8"	FOOT	1012		1012	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	871	42	829	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	12		12	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	44	5	39	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	7	1	6	
78300100	PAVEMENT MARKING REMOVAL	SO FT	5168	1131	4037	
Δ X0320157	CLEANING UNDERDRAIN OUTLETS	EACH	68		68	
X0323583	SPEED INDICATOR SIGN	CAL DA	200	10	190	
X4060655	TEST STRIP (STONE MATRIX ASPHALT)	EACH	1	0.05	0.95	
X4063500	PRELIMINARY TEST STRIP	EACH	1	0.05	0.95	

SUMMARY OF QUANTITIES			90% FED./10% STATE	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CLAY COUNTY	EFFINGHAM COUNTY	
				0004	0004	0014
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	4176	1268	2908	
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SO FT	240		240	
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	14	1	13	
X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	766		766	
X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	100		100	
XZ193500	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4"	SO YD	1623			1623
Z0006220	BRIDGE DECK HYDRO-SCARIFICATION 2 1/4"	SO YD	1623			1623
Z0012710	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL	EACH	57	8	49	
Z0015802	PLUG EXISTING DECK DRAINS	EACH	4			4
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SO YD	1			1
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SO YD	81			81
Z0016702	DETOUR SIGNING	L SUM	1		1	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	1		3
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1		1	
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	1		1	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	1		3
Z0034105	MATERIAL TRANSFER DEVICE	TON	20692	1294	19398	
Z0049790	RELOCATING NAME PLATES	EACH	2			2
Z0055605	RUBBLIZING PORTLAND CEMENT CONCRETE PAVEMENT	SO YD	22861	2431	20430	
Ⓞ Z0076600	TRAINEES	HOUR	500		500	

* Specialty Items
Δ = NON-PARTICIPATING

© 0042

Rev. 1-4-2011

Rev.

FILE NAME -	USER NAME - teasleyk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pwwork\pwwork\teasleyk\00148697\07	4417-shr-soa.dgn	DRAWN -	REVISED -			57	(13-1)R&(25-6-1)R	.	44	4
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 74417				
PLOT DATE = 10/22/2010		DATE -	REVISED -			ILLINOIS FED. AID PROJECT				