

| SUMMARY OF QUANTITIES | | | 90% FED./10% STATE | CONSTRUCTION TYPE CODE | | |
|-----------------------|---|------------------|--------------------|------------------------|------------------|------|
| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | CLAY COUNTY | EFFINGHAM COUNTY | |
| | | | | 0004 | 0004 | 0014 |
| 70100460 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 | L SUM | 1 | | 1 | |
| 70100600 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701336 | L SUM | 1 | | 1 | |
| 70100700 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701406 | L SUM | 1 | | 1 | |
| 70100800 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701401 | L SUM | 1 | | 1 | |
| 70100820 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701451 | L SUM | 1 | | 1 | |
| 70100825 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701456 | L SUM | 1 | | 1 | |
| 70103815 | TRAFFIC CONTROL SURVEILLANCE | CAL DA | 10 | | 10 | |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 7595 | 306 | 7289 | |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 84860 | 3726 | 81134 | |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SO FT | 2229 | 102 | 2127 | |
| 70400100 | TEMPORARY CONCRETE BARRIER | FOOT | 6600 | 875 | 5725 | |
| 70400200 | RELOCATE TEMPORARY CONCRETE BARRIER | FOOT | 6425 | 875 | 5550 | |
| * 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SO FT | 93.6 | | 93.6 | |
| * 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 22300 | | 22300 | |
| * 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 500 | | 500 | |
| * 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 80 | | 80 | |
| * 78004210 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4" | FOOT | 59164 | 3301 | 55863 | |
| * 78004230 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6" | FOOT | 7690 | 425 | 7265 | |
| * 78004240 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 8" | FOOT | 1012 | | 1012 | |
| * 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 871 | 42 | 829 | |
| * 78100105 | RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) | EACH | 12 | | 12 | |
| * 78200410 | GUARDRAIL MARKERS, TYPE A | EACH | 44 | 5 | 39 | |
| * 78201000 | TERMINAL MARKER - DIRECT APPLIED | EACH | 7 | 1 | 6 | |
| 78300100 | PAVEMENT MARKING REMOVAL | SO FT | 5168 | 1131 | 4037 | |
| Δ X0320157 | CLEANING UNDERDRAIN OUTLETS | EACH | 68 | | 68 | |
| X0323583 | SPEED INDICATOR SIGN | CAL DA | 200 | 10 | 190 | |
| X4060655 | TEST STRIP (STONE MATRIX ASPHALT) | EACH | 1 | 0.05 | 0.95 | |
| X4063500 | PRELIMINARY TEST STRIP | EACH | 1 | 0.05 | 0.95 | |

| SUMMARY OF QUANTITIES | | | 90% FED./10% STATE | CONSTRUCTION TYPE CODE | | |
|-----------------------|---|--------|--------------------|------------------------|------------------|------|
| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | CLAY COUNTY | EFFINGHAM COUNTY | |
| | | | | 0004 | 0004 | 0014 |
| X4401198 | HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH | SO YD | 4176 | 1268 | 2908 | |
| X4402020 | CONCRETE MEDIAN SURFACE REMOVAL | SO FT | 240 | | 240 | |
| X7015005 | CHANGEABLE MESSAGE SIGN | CAL DA | 14 | 1 | 13 | |
| X7830070 | GROOVING FOR RECESSED PAVEMENT MARKING 5" | FOOT | 766 | | 766 | |
| X7830074 | GROOVING FOR RECESSED PAVEMENT MARKING 7" | FOOT | 100 | | 100 | |
| XZ193500 | BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4" | SO YD | 1623 | | | 1623 |
| Z0006220 | BRIDGE DECK HYDRO-SCARIFICATION 2 1/4" | SO YD | 1623 | | | 1623 |
| Z0012710 | CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL | EACH | 57 | 8 | 49 | |
| Z0015802 | PLUG EXISTING DECK DRAINS | EACH | 4 | | | 4 |
| Z0016001 | DECK SLAB REPAIR (FULL DEPTH, TYPE I) | SO YD | 1 | | | 1 |
| Z0016002 | DECK SLAB REPAIR (FULL DEPTH, TYPE II) | SO YD | 81 | | | 81 |
| Z0016702 | DETOUR SIGNING | L SUM | 1 | | 1 | |
| Z0030250 | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 4 | 1 | | 3 |
| Z0030260 | IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3 | EACH | 1 | | 1 | |
| Z0030330 | IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3 | EACH | 1 | | 1 | |
| Z0030350 | IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 4 | 1 | | 3 |
| Z0034105 | MATERIAL TRANSFER DEVICE | TON | 20692 | 1294 | 19398 | |
| Z0049790 | RELOCATING NAME PLATES | EACH | 2 | | | 2 |
| Z0055605 | RUBBLIZING PORTLAND CEMENT CONCRETE PAVEMENT | SO YD | 22861 | 2431 | 20430 | |
| Ⓞ Z0076600 | TRAINEES | HOUR | 500 | | 500 | |

* Specialty Items
Δ = NON-PARTICIPATING

© 0042

Rev. 1-4-2011

Rev.

| | | | | | | | | | | | |
|--|----------------------|------------|-----------|---|------------------------------|--------------------|---------------------|--------------|---------------------------|-----------|--|
| FILE NAME - | USER NAME - teasleyk | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. | |
| ct:\pwwork\pwwork\teasleyk\00148697\07 | 4417-shr-soa.dgn | DRAWN - | REVISED - | | | 57 | (13-1)R&(25-6-1)R | . | 44 | 4 | |
| PLOT SCALE = 100.0000' / IN. | | CHECKED - | REVISED - | | | CONTRACT NO. 74417 | | | | | |
| PLOT DATE = 10/22/2010 | | DATE - | REVISED - | | | SCALE: | SHEET NO. OF SHEETS | STA. TO STA. | ILLINOIS FED. AID PROJECT | | |