

SUMMARY OF QUANTITIES

*URBAN
90% FED. / 10% STATE*

*URBAN
90% FED.
10% STATE*

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE 0021 TOTAL QUANTITIES
CODE NO	ITEM	UNIT	TOTAL QUANTITIES
25000210	SEEDING, CLASS 2A	ACRE	0.8
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	78
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	78
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	78
25100105	MULCH, METHOD 1	ACRE	0.8
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	87
28000500	INLET AND PIPE PROTECTION	EACH	12
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7
67100100	MOBILIZATION	L SUM	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	9
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1
80300100	LOCATING UNDERGROUND CABLE	FOOT	7560
80500100	SERVICE INSTALLATION, TYPE A	EACH	1
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	130
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	140
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	15
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	2
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	500
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	7560
83060830	LIGHT POLE, GALVANIZED STEEL, 45 FT. M. H., TENON MOUNT	EACH	1
83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	13.5
87100110	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 6F	FOOT	2810
87900100	DRILL EXISTING FOUNDATION	EACH	2
87900200	DRILL EXISTING HANDHOLE	EACH	1
X0323150	JUNCTION BOX, ALUMINUM, ATTACHED TO STRUCTURE, 18" X 18" X 10"	EACH	2
X0325073	MODIFY EXISTING CONTROLLER CABINET TYPE B	EACH	1
X0325075	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., FIBERGLASS BULLET RESISTANT	FOOT	60
X0325076	WIDE AREA NETWORK	L SUM	1
X0325077	FIBER OPTIC UTILITY MARKER	EACH	25

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE 0021 TOTAL QUANTITIES
CODE NO	ITEM	UNIT	TOTAL QUANTITIES
X0325476	RADAR VEHICLE DETECTION SYSTEM	EACH	1
X0325482	REMOVE EXISTING ITS EQUIPMENT	EACH	2
X0325483	SFP-GE-L SFP MODULE	EACH	4
X0325487	WIRED COMMUNICATION DATA CONVERTOR	EACH	2
X0326091	LIGHT POLE, STEEL 50 FT. WITH CAMERA LOWERING SYSTEM	EACH	1
X0326092	RELOCATE CLOSED CIRCUIT TELEVISION SURVEILLANCE CAMERA SYSTEM	EACH	1
X0326104	RELOCATE RADAR DETECTOR SYSTEM	EACH	1
X0326259	DIGITAL VIDEO ENCODER	EACH	1
X0326342	DIGITAL VIDEO DECODER	EACH	1
X0326912	3000 LAYER 2 SWITCH	EACH	1
X8100065	CONDUIT IN TRENCH, 4" DIA., PVC TYPE C	FOOT	7290
X8102020	CONDUIT PUSHED, 4" DIA., PVC SCHEDULE 80	FOOT	350
X8110128	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., PVC TYPE C	FOOT	180
X8710075	FIBER OPTIC CABLE IN CONDUIT, 72 COND. S.M. F.O.	FOOT	8020
X8130250	JUNCTION BOX, ALUMINUM, ATTACHED TO STRUCTURE, 24" X 20" X 10"	EACH	1
X0327096	ETHERNET MODEM	EACH	2
Z0033090	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	7130
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1

Rev.