

CLASS B PAVEMENT PATCHING 10" INCH SCHEDULE										
LOCATION	LANE	LENGTH	LANE WIDTH	CLASS B PATCH TYPE II	CLASS B PATCH TYPE III	CLASS B PATCH TYPE IV	DOWEL BARS 1 1/2"	TIE BARS 3/4"	PAVEMENT FABRIC	SAWCUT
		(FT)	(FT)	(SQ YD)	(SQ YD)	(SQ YD)	(EACH)		(SQ YD)	(FT)
RAMP A							20			
0 + 10		50.0	6.0			33.3	20	25	33.3	124.0
RAMP B										
14 + 30	LT	6.0	12.0	8.0			20			60.0
14 + 32	RT	150.0	4.0			66.7	20	75	66.7	316.0
15 + 30	RT	6.0	12.0	8.0			20			60.0
16 + 50	RT	6.0	16.0	10.7			28			76.0
16 + 50	LT	6.0	16.0	10.7			28			76.0
17 + 50	RT	6.0	17.0	11.3			28			80.0
17 + 50	LT	6.0	17.0	11.3			28			80.0
18 + 20	RT	6.0	18.0	12.0			28			84.0
18 + 20	LT	6.0	18.0	12.0			28			84.0
19 + 65		25.0	30.0			83.3	28	13	83.3	170.0
RAMP C							20			
13 + 30		6.0	16.0	10.7			28			76.0
13 + 90		6.0	16.0	10.7			28			76.0
15 + 20		6.0	19.0	12.7			28			88.0
15 + 50		6.0	21.0	14.0			28			96.0
16 + 20	RT	6.0	12.0	8.0			20			60.0
16 + 20	LT	6.0	12.0	8.0			20			60.0
16 + 75	RT	6.0	12.0	8.0			20			60.0
16 + 75	LT	6.0	12.0	8.0			20			60.0
16 + 90	RT	280.0	6.0			186.7	20	140	186.7	584.0
17 + 00	RT	6.0	16.0	10.7			28			76.0
18 + 00	RT	8.0	18.0		16.0		28		16.0	88.0
RAMP D							20			
1 + 50		6.0	16.0	10.7			28			76.0
SUBTOTAL:				185.3	16.0	336.7	592.0	227.5	352.7	2486.0
ANTICIPATED FAILURES (15%):				27.8	2.4	50.5	3.0	3.0	3.0	372.9
TOTAL:				213	18	387	595	231	356	2859

CLASS A PAVEMENT PATCHING 11" INCH SCHEDULE										
LOCATION	LANE	LENGTH	LANE WIDTH	CLASS A PATCH TYPE III	CLASS A PATCH TYPE IV	PATCHING REINF.	TIE BARS 3/4"	PAVEMENT FABRIC	SAWCUT	
		(FT)	(FT)	(SQ YD)	(SQ YD)	(SQ YD)	(EACH)	(SQ YD)	(FT)	
IL 159										
28 + 63	MIDDLE	130.0	20.0	288.9	288.9	65	288.9	340.0		
36 + 15	NB	8.0	36.0	32.0	32.0		32.0	160.0		
36 + 15	SB	8.0	24.0	21.3	21.3		21.3	112.0		
38 + 75	MIDDLE	85.0	20.0	188.9	188.9	43	188.9	250.0		
SUBTOTAL:				21.3	509.8	531.1	107.5	531.1	862.0	
ANTICIPATED FAILURES (15%):				3.2	76.5	3.0	3.0	3.0	129.3	
TOTAL:				25	586	534	111	534	991	

GUARDRAIL REMOVAL				
LOCATION			RT/LT	GUARDRAIL REMOVAL (FOOT)
STA	TO	STA		
IL 159				
32+40	TO	33+77.5	RT	137.5
32+74	TO	33+86.55	LT	112.5
36+20.9	TO	37+70.9	LT	150
TOTAL :				400

TREE REMOVAL				
LOCATION			TREE REMOVAL (6 TO 15 UNITS)	TREE REMOVAL (6 TO 15 UNITS)
			(UNITS)	(UNITS)
IL 159				
23+44	TO	30+00	14	
36+00	TO	40+00	230	50
RAMP F				
0+00	TO	24+50	206	18
TOTAL:			450	68

COMBINATION CURB AND GUTTER REMOVAL				
LOCATION			AREA	REMOVAL (FOOT)
STA	TO	STA		
IL 159				
28+41.15	TO	28+87.54	MEDIAN	103
29+52	TO	33+84.25	MEDIAN	865
38+49.89	TO	39+18.89	MEDIAN	142
RAMP "B"				
19+63	TO	19+77	ISLAND	65
TOTAL:				1175

MEDIAN REMOVAL			
LOCATION			AREA (SQ FT)
STA	TO	STA	
IL 159			
28+41.7	TO	28+87.54	486
29+52	TO	33+84.6	3325
38+50.4	TO	39+18.89	929
RAMP "B"			
19+63	TO	19+77 (ISLAND)	195
TOTAL:			4935

REMOVING EXISTING UNDERDRAINS				
LOCATION			RT/LT	FOOT
STA	TO	STA		
IL 159				
23+81.92	TO	1+88 (RAMP D)	RT	593
29+4.5	TO	33+84.25	LT	480
36+20.2	TO	39+85.27	LT	365
RAMP "B"				
14+32.74	TO	18+77.30	RT	418
17+21	TO	19+71.27	LT	250
RAMP "C"				
13+14.61	TO	19+13.23	LT	599
TOTAL :				2705

PAVED SHOULDER REMOVAL				
LOCATION			RT/LT	AREA (SQ YD)
STA	TO	STA		
IL 159				
23+81.92	TO	1+88 (RAMP D)	RT	539
29+4.5	TO	33+84.25	LT	140
36+20.2	TO	39+85.27	LT	404
RAMP B				
14+32.74	TO	18+77.30	RT	270
17+21	TO	19+71.27	LT	139
RAMP C				
13+14.61	TO	19+24.53	LT	290
RAMP F				
11+38	TO	24+50	RT	1469
FAI ROUTE 64				
536+35	TO	536+87	MEDIAN	92
TOTAL :				3343

FILE NAME =	USER NAME = burnsideem	DESIGNED -	REVISED -
c:\pwork\pwork\burnsideem\d0166383\876d59-shr-plan.dgn		DRAWN -	REVISED -
PLOT SCALE = 1/8" = 1' IN.		CHECKED -	REVISED -
PLOT DATE = 1/4/2011		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

Rev. Sheet 1-3-11

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-5-2	ST CLAIR	162	20
CONTRACT NO. 76D59				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				