

RESURFACING SCHEDULE						
LOCATION			BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	LEVELING BINDER (MACHINE METHOD) IL-9.5FG, N90, 1"	POLYMERIZED HMA SURFACE COURSE, 1 1/2"
LOCATION			(TON)	(TON)	(TON)	(TON)
RAMP "A"						
0+89	TO	10+67.1	1.1	5.2	98	146
RAMP "B"						
6+80	TO	14+27.74	1.1	5.5	102	154
RAMP "C"						
4+78.5	TO	13+09.61	1.0	4.4	83	124
RAMP "D"						
1+93	TO	10+14	0.9	4.4	82	123
RAMP "E"						
2+55.5	TO	10+51.7	1.0	4.6	86	129
TOTAL:			5.1	24.1	451	676

SHOULDER RESURFACING SCHEDULE						
LOCATION			BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	AGGREGATE WEDGE SHOULDER, TYPE B	HMA SHOULDERS, 2 1/2"
LOCATION			(TON)	(TON)	(TON)	(TON)
RAMP "A"						
0+89	TO	10+67.1	0.7	3.3	31.7	152
RAMP "B"						
6+80	TO	14+27.74	0.5	2.5	24.2	118
RAMP "C"						
4+78.5	TO	13+09.61	0.6	2.8	26.9	129
RAMP "D"						
1+93	TO	10+14	0.6	2.7	26.6	128
RAMP "E"						
2+55.5	TO	10+51.7	0.7	3.1	25.8	146
TOTAL:			3.0	14.4	136.0	673

CLASS B PAVEMENT PATCHING 10" INCH SCHEDULE						
LOCATION	LANE	LENGTH	LANE WIDTH	CLASS B PATCH TYPE II	DOWEL BARS 1 1/2"	SAWCUT
		(FT)	(FT)	(SQ YD)	(EACH)	(FT)
RAMP "A"						
1	+	41.8	6.0	16.0	10.7	28
1	+	94.6	6.0	16.0	10.7	28
2	+	47.4	6.0	16.0	10.7	28
2	+	73.8	6.0	16.0	10.7	28
3	+	0.2	6.0	16.0	10.7	28
3	+	53	6.0	16.0	10.7	28
4	+	5.8	6.0	16.0	10.7	28
4	+	58.6	8.0	16.0	14.2	28
6	+	17	6.0	16.0	10.7	28
RAMP "B"						
7	+	82.4	8.0	16.0	14.2	28
8	+	37.3	LT	8.0	6.0	5.3
8	+	37.3	RT	8.0	6.0	5.3
9	+	44.7	LT	8.0	6.0	5.3
9	+	44.7	CENTER	8.0	6.0	5.3
9	+	44.7	RT	8.0	6.0	5.3
-11	+	49.2	LT	6.0	12.0	8.0
12	+	59.6	LT	6.0	12.0	8.0
13	+	52.8	LT	6.0	12.0	8.0
13	+	52.8	RT	6.0	12.0	8.0
RAMP "C"						
12	+	59	6.0	16.0	10.7	28
RAMP "D"						
4	+	4.2	6.0	16.0	10.7	28
4	+	57	6.0	16.0	10.7	28
5	+	62.6	6.0	16.0	10.7	28
7	+	73.8	8.0	16.0	14.2	28
9	+	58.6	6.0	8.0	5.3	20
9	+	85	6.0	16.0	10.7	28
				245.3	648.0	1712.0
ANTICIPATED FAILURES (15%):				36.8	97.2	256.8
TOTAL:				282	745	1969

TEMPORARY RAMPS	
LOCATION	TEMPORARY RAMPS (SQ YD)
RAMP "A"	
10+67.1	8.9
RAMP "B"	
6+80	9.4
RAMP "C"	
4+78.5	8.9
RAMP "D"	
10+14	8.9
RAMP "E"	
10+51.7	8.9
TOTAL:	45

PAVEMENT MARKING SCHEDULE									
LOCATION			TEMPORARY PAVEMENT MARKING		PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID		SHORT-TERM PAVEMENT MARKING (3 LIFTS)	SHORT-TERM PAVEMENT MARKING (3 LIFTS)	WORKZONE PAVEMENT MARKING REMOVAL
STA	TO	STA	LINE, 4" SOLID (WHITE)	LINE, 4" SOLID (YELLOW)	LINE, 4" SOLID (WHITE)	LINE, 4" SOLID (YELLOW)	(WHITE)	(YELLOW)	SQ FT
RAMP "A"									
0+89	TO	10+67.1	978	978	978	978	267	267	59
RAMP "B"									
6+80	TO	14+27.74	748	748	748	748	204	204	45
11+90	TO	14+27.74	233		233		64		7
RAMP "C"									
4+78.5	TO	13+09.61	831	831	831	831	227	227	50
RAMP "D"									
1+93	TO	10+14	821	821	821	821	224	224	50
RAMP "E"									
2+55.5	TO	10+51.7	796	796	796	796	217	217	48
SUB TOTAL:			4407	4174	4407	4174	1202	1138	260
TOTAL:			8581		8581		2340		260

PCC SURFACE REMOVAL - BUTT JOINTS	
LOCATION	BUTT JOINTS (SQ YD)
RAMP "A"	
10+67.1	53
RAMP "B"	
6+80	57
RAMP "C"	
4+78.5	53
RAMP "D"	
10+14	53
RAMP "E"	
10+51.7	53
TOTAL:	270