

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

90% FED.
 10% STATE
 TOTAL
 QUANTITIES

CONSTRUCTION TYPE CODE

CODE NO	ITEM	UNIT	URBAN	0005	0011	0021	0021	0005			
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	450	450							
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	68	68							
20200100	EARTH EXCAVATION	CU YD	2489	2489							
20400800	FURNISHED EXCAVATION	CU YD	43032	43032							
20700220	POROUS GRANULAR EMBANKMENT	CU YD	12	12							
25000200	SEEDING, CLASS 2	ACRE	6.3	6.3							
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	564	564							
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	564	564							
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	564	564							
25100105	MULCH, METHOD 1	ACRE	6.3	6.3							
25100630	EROSION CONTROL BLANKET	SQ YD	18717	18717							
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1253	1253							
28000305	TEMPORARY DITCH CHECKS	FOOT	286	286							
28000400	PERIMETER EROSION BARRIER	FOOT	2487	2487							
28000500	INLET AND PIPE PROTECTION	EACH	4	4							
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	1060	1060							
28200200	FILTER FABRIC	SQ YD	1060	1060							
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	6358	6358							
35300410	PORTLAND CEMENT CONCRETE BASE COURSE 9 1/2"	SQ YD	1187	1187							
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	32.6	24.5				8.1			
40600300	AGGREGATE (PRIME COAT)	TON	90.8	52.3				38.5			
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	1259	808				451			
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	270					270			
40600990	TEMPORARY RAMP	SQ YD	345	300				45			
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	1095	1095							
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	2252	1576				676			
40702001	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 16"	SQ YD	3705	3705							
42001200	PAVEMENT FABRIC	SQ YD	356	356							
42001300	PROTECTIVE COAT	SQ YD	1,061	1,061							
44000100	PAVEMENT REMOVAL	SQ YD	66	66							
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1038	1038							
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	14014	14014							
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1175	1175							
X4401980	CONCRETE BARRIER REMOVAL	FOOT	52	52							
44003100	MEDIAN REMOVAL	SQ FT	4935	4935							

Rev. 1-10-11
 Rev. 1-6-11