

WRB

ILLINOIS DEPARTMENT OF TRANSPORTATION			90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		0005	0011	0021	0021	0005
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	450	450				
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	68	68				
20200100	EARTH EXCAVATION	CU YD	2489	2489				
20400800	FURNISHED EXCAVATION	CU YD	43032	43032				
20700220	POROUS GRANULAR EMBANKMENT	CU YD	12	12				
25000200	SEEDING, CLASS 2	ACRE	6.3	6.3				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	564	564				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	564	564				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	564	564				
25100105	MULCH, METHOD 1	ACRE	6.3	6.3				
25100630	EROSION CONTROL BLANKET	SQ YD	18717	18717				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1253	1253				
28000305	TEMPORARY DITCH CHECKS	FOOT	286	286				
28000400	PERIMETER EROSION BARRIER	FOOT	2487	2487				
28000500	INLET AND PIPE PROTECTION	EACH	4	4				
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	1060	1060				
28200200	FILTER FABRIC	SQ YD	1060	1060				
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	6358	6358				
35300410	PORTLAND CEMENT CONCRETE BASE COURSE 9 1/2"	SQ YD	1187	1187				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	32.6	24.5			8.1	
40600300	AGGREGATE (PRIME COAT)	TON	90.8	52.3			38.5	
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	1259	808			451	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	270				270	
40600990	TEMPORARY RAMP	SQ YD	345	300			45	
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	1095	1095				
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	2252	1576			676	
40702001	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 16"	SQ YD	3705	3705				
42001200	PAVEMENT FABRIC	SQ YD	890	890				
42001300	PROTECTIVE COAT	SQ YD	1047	1047				
44000100	PAVEMENT REMOVAL	SQ YD	66	66				
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1038	1038				
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	14014	14014				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1175	1175				
X4401980	CONCRETE BARRIER REMOVAL	FOOT	52	52				
44003100	MEDIAN REMOVAL	SQ FT	4935	4935				

FILE NAME =	USER NAME = burnsideem	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.				
ca:\pwork\pwork\burnsideem\2166363\176499-shr-plan.dgn		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	64	82-5K-2	ST. CLAIR	162	5
PLOT SCALE = 50.0000' / 1" IN.		CHECKED -	REVISED -						CONTRACT NO. 76D59								
PLOT DATE = 8/11/2010		DATE -	REVISED -														