

SIGNING												
LOCATION			REMOVE SIGN PANEL ASSEMBLY TYPE A	REMOVE SIGN PANEL ASSEMBLY TYPE B	REMOVE SIGN PANEL TYPE 3	WOOD SIGN SUPPORT	OVERHEAD SIGN STRUCTURE - CANTILEVER TYPE II-C-A	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	DRILLED SHAFT CONCRETE FOUNDATIONS	SIGN PANEL TYPE 1	SIGN PANEL TYPE 2	SIGN PANEL TYPE 3
STA	LT/RT	OFFSET	(EACH)	(EACH)	(SQ FT)	(FOOT)	(FOOT)	(FOOT)	(CU YDS)	(SQ FT)	(SQ FT)	(SQ FT)
IL 159												
23+60	MEDIAN		1							5		
23+60	MEDIAN					12.0						
24+87	RT	69'										156
28+40	RT	79'		1								
28+80	MEDIAN			1								
28+95	MEDIAN					12.0				5		
28+95	MEDIAN									9		
29+20	LT	54'	1									
29+49	LT	64'		1								
29+50	LT	48'	1									
29+59	MEDIAN			1								
29+67	MEDIAN					12.0				5		
29+67	MEDIAN									9		
33+40	MEDIAN			1								
33+45	LT	48'	1									
33+90	LT	61.3'					30	30	6.1			156
36+22	MEDIAN			1								
38+99	MEDIAN					12.0				5		
38+99	MEDIAN									9		
39+81	MEDIAN		1									
39+81	MEDIAN					12.0				5		
41+50	LT	77'			348.75							348.75
RAMP B												
17+98	LT	40'	1									
18+02	LT	44'				13.4				8.75		
17+98	RT	35'	1									
18+02	RT	35'				13.4				8.75		
19+00	LT	40'	1									
19+00	LT	46'				13.4				9		
RAMP C												
17+00	LT	30'	1									
17+00	LT	32'				13.2				8.75		
18+00	LT	41'	1							9		
18+00	LT	45'				14.3						
19+05	MEDIAN			1								
RAMP F												
0+90	RT	60'				13.6				5		
10+75	LT	32'				14.0					16	
19+89	RT	7.5'	1								12	
19+89	RT	16'				13.0				6		
20+82	RT	10'		1								
20+82	RT	16'				13.0					16	
TOTAL :			11	8	348.75	181.0	30.0	30.0	6.1	107.25	44	660.75

PIPE UNDERDRAINS, 6" (SPECIAL)			
STA	RT/LT	PIPE UNDERDRAINS, 6" (SPECIAL) (FOOT)	CONCRETE HEADWALL (EACH)
IL 159			
27+00	RT	3.5	1
29+50	LT	16.5	1
37+50	LT	11.5	1
RAMP B			
14+32.74	RT	6.5	1
14+32.74	LT	3.5	1
17+21	LT	3.5	1
18+50	RT	9.5	1
RAMP C			
13+14.61	LT	4.5	1
16+00	LT	11.5	1
RAMP D			
1+88	RT	16.5	1
LOOP RAMP F			
4+50	LT	7.5	1
5+00	RT	9.5	1
9+50	RT	8.5	1
10+00	LT	8.5	1
12+50	RT	9.5	1
17+00	RT	9.5	1
22+00	RT	9.5	1
TOTAL:		150	17

PIPE UNDERDRAINS, 6"				
LOCATION			RT/LT	FOOT
STA	TO	STA		
IL 159				
23+81.92	TO	1+88 (RAMP D)	RT	593
29+22.15	TO	32+33.72	LT	312
36+20.2	TO	39+85.27	LT	365
RAMP "B"				
14+32.74	TO	18+77.30	RT	418
17+21	TO	19+59.54	LT	239
RAMP "C"				
13+14.61	TO	19+12.6	LT	598
LOOP RAMP F				
0+00	TO	23+63	RT	2350
1+54.4	TO	11+38	LT	984
TOTAL :				5858