

SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0014		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1.7	1.7		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	350	350		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
Z0001905	STRUCTURAL STEEL REPAIR	POUND	5930	5930		

GENERAL NOTES:

1. THE STANDARDS AND REVISION NUMBERS SHALL APPLY TO THIS PROJECT.
2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
3. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO ALL UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
 - AT&T ILLINOIS
 - CITY OF CENTRALIA (WATER & SANITARY SEWER)
 - CLINTON COUNTY ELECTRIC COOPERATIVE
 - HOFFMAN RURAL WATER DISTRICT
 - HOYLETON RURAL WATER COMPANY
 - PAETEC/MCLEOD USA TELECOMMUNICATIONS, INC.
MEMBERS OF J.U.L.I.E. (800) 892-0123 OR 811 ARE INDICATED BY AN •. NON-J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.
4. "ROAD CONSTRUCTION AHEAD" SIGNS SHALL BE PLACED AT EACH END OF THE PROJECT AND ALL INTERSECTING SIDE ROADS AND WILL BE INCLUDED IN THE TRAFFIC CONTROL PAY ITEMS. ALL CONSTRUCTION SIGNS SHALL BE FLOURESCENT ORANGE, 48".
5. THE REMOVAL AND REPLACEMENT OF THE 1' x 1' POUR HOLE AS SHOWN IN THE DETAIL FOR PIER #3 SHALL BE INCLUDED IN THE COST OF "CONCRETE SUPERSTRUCTURE" AND NO OTHER COMPENSATION WILL BE PERMITTED.

PERTINENT INFORMATION

THE CONTRACTOR SHALL BE AWARE THAT THERE ARE WETLANDS LOCATED WITHIN THE RIGHT OF WAY ON THE NORTH SIDE OF THE STRUCTURE. IN ORDER TO ACCESS THE SITE, THE CONTRACTOR SHALL BE PERMITTED TO TRANSPORT HIS EQUIPMENT ALONG THE TOE OF SLOPE. HOWEVER, HE SHOULD TAKE CARE TO MINIMIZE DAMAGE TO THE WETLANDS.

COMMITMENTS

NONE