

GENERAL NOTES

- 1) THE THICKNESS OF HOT-MIX ASPHALT MIXTURE SHOWN ON THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HOT-MIX ASPHALT MIXTURE IS PLACED.
- 2) FACTORS USED FOR ESTIMATING PLAN QUANTITIES ARE AS FOLLOWS AND SHALL NOT BE USED FOR THE BASIS OF FINAL QUANTITIES:
- |                                  |                  |
|----------------------------------|------------------|
| ALL HOT MIX ASPHALT              | 2.016 TONS/CU YD |
| BITUMINOUS MATERIALS ON PAVEMENT | 0.09 GAL/SQ YD   |
| INTERMEDIATE LIFTS (FOG COAT)    | 0.04 GAL/SQ YD   |
- 3) PRIOR TO PLACEMENT OF THE FINAL PAVEMENT MARKINGS THE RESIDENT ENGINEER SHOULD CONTACT THE BUREAU OF OPERATIONS AND ARRANGE FOR INSPECTION AND APPROVAL OF THE PAVEMENT MARKING LAYOUT.
- 4) IN ADDITION TO THE REQUIREMENTS OF ARTICLE 107.16 THE CONTRACTOR SHALL PROTECT THE SURFACE OF ALL BRIDGE DECKS AND BRIDGE APPROACH PAVEMENTS IN A MANNER SATISFACTORY TO THE ENGINEER BEFORE ANY EQUIPMENT IS ALLOWED TO CROSS THE STRUCTURE. PROTECTION SHALL BE PROVIDED FOR ALL EQUIPMENT AS DEFINED IN ARTICLE 101.16 REGARDLESS IF TRACK MOUNTED OR WHEELED.
- 5) COMMITMENTS: NONE AS OF 10/27/10.

INDEX OF SHEETS

- 1 COVER SHEET
- 2 SIGNATURES, INDEX OF SHEETS, STANDARDS, GENERAL NOTES
- 3 SUMMARY OF QUANTITIES
- 4 GENERAL PLAN & ELEVATION
- 5 NOTES, MIXTURE REQUIREMENTS
- 6-9 JOINT REPLACEMENT DETAILS
- 10 PREFORMED JOINT STRIP SEAL DETAILS
- 11 ALUMINUM RAILING (FOR INFORMATION)
- 12 RESURFACING
- 13 EROSION REPAIR
- 14,15 BEARING REPLACEMENT DETAILS

STANDARDS

- |           |   |
|-----------|---|
| 000001-06 | STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS              |
| 001001-02 | AREAS OF REINFORCEMENT BARS                               |
| 635011-02 | REFLECTOR MARKER AND MOUNTING DETAILS                     |
| 701451-01 | RAMP CLOSURE, FREEWAY/EXPRESSWAY                          |
| 780001-02 | TYPICAL PAVEMENT MARKINGS                                 |
| 781001-03 | TYPICAL APPLICATION OF RAISED REFLECTIVE PAVEMENT MARKERS |
| 701901-01 | TRAFFIC CONTROL DEVICES                                   |

Prepared By: *[Signature]*  
DISTRICT STUDIES & PLANS ENGINEER

Examined By: *[Signature]*  
DISTRICT LAND ACQUISITION ENGINEER

Examined By: *[Signature]*  
DISTRICT PROGRAM DEVELOPMENT ENGINEER

Examined By: *[Signature]*  
DISTRICT OPERATIONS ENGINEER

Examined By: *[Signature]*  
DISTRICT CONSTRUCTION ENGINEER

Examined By: *[Signature]*  
DISTRICT MATERIALS ENGINEER

Examined By: *[Signature]*  
DISTRICT PROJECT IMPLEMENTATION ENGINEER

Examined By: *[Signature]*  
ASSISTANT REGIONAL ENGINEER

Approved By: *[Signature]*  
DEPUTY DIRECTOR OF HIGHWAYS, REGION 5 ENGINEER

Nov 9 2010  
DATE

USER NAME = gautneyrk	DESIGNED - RKG	REVISED -
DRAWN - RKG	REVISED -	
PLOT SCALE = 25:11x2 1/4 " = 1' IN.	CHECKED - MAS	REVISED -
PLOT DATE = 10/26/2010	DATE - 10/27/10	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

INDEX OF SHEETS, GENERAL NOTES, STANDARDS

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	D9 CM BRIDGE REPAIR 2011-1	JEFFERSON	15	2
CONTRACT NO. 78212				
ILLINOIS FED. AID PROJECT				