

**SUMMARY OF QUANTITIES**

IM FUNDING  
90% FEDERAL 10% STATE  
CONSTRUCTION TYPE CODE  
0005  
WILLIAMSON  
SN 100-0009

CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY
44001114	HOT-MIX ASPHALT SURFACE REMOVAL (ASBESTOS)	SQ YD	1030
<del>42001300</del>	<del>PROTECTIVE COAT</del>	<del>SQ YD</del>	<del>1030</del>
50300260	BRIDGE DECK GROOVING	SQ YD	998
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	2
67100100	MOBILIZATION	L SUM	1
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	1
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	3
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	50
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	528
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	193
70400100	TEMPORARY CONCRETE BARRIER	FOOT	425
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	387.5
* 78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	528
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	4
78300100	PAVEMENT MARKING REMOVAL	SQ FT	175
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	4
X0323644	PAVEMENT MARKING GROOVING	FOOT	528
XZ191205	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 3'	SQ YD	1030
Z0006202	BRIDGE DECK HYDRO-SCARIFICATION 3/4"	SQ YD	1030
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	1
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	21
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1
Z0041895	POLYMER CONCRETE	CU FT	5.8

\*Specialty Items

FILE NAME =	USER NAME = ha.steadtw	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cc:\pw\work\p\wdct\ha\steadtw\100235582\1120-0008-0009_sht-plm.dgn	PLLOT SCALE = 50.0000 1/1 IN.	DRAWN -	REVISED -			57	D9 BSMART 2011-1	WILLIAMSON	11	3
PLLOT DATE = 9/28/2010	DATE -	CHECKED -	REVISED -			SHEET NO. OF SHEETS		CONTRACT NO. 78226		
						ILLINOIS FED. AID PROJECT				

Rev.