



PLAN

NUMBER	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)
1	8	2	1.8
2	5	3	1.7
3	10	2	2.2
4	6	2	1.3
* 5	2	2	0.4
* 6	8	2	1.8
* 7	2	2	0.4
8	10	2	2.2
9	5	4	2.2
10	5	2	1.1
11	10	4	4.5
12	10	2	2.2

* Indicates Type I patches

Notes: Deck Survey was performed in June 2010
 The Resident Engineer will determine final patch locations and quantities in the field before bridge deck patching operations begin.
 Areas of deck repairs shown are estimated. The Engineer shall show actual locations of deck repairs on As-built Plans.
 The existing protective shield shall remain in place.

BILL OF MATERIAL

Item	Unit	Total
Deck Slab Repair (Full Depth, Type I)	Sq Yd	1
Deck Slab Repair (Full Depth, Type II)	Sq Yd	21

**DECK SLAB REPAIRS
 WILLIAMSON COUNTY
 STRUCTURE NO. 100-0009 (S.B.)**

FILE NAME =	USER NAME = halsteadtw	DESIGNED - TWH	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	DECK SLAB REPAIRS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pwwork\pwwork\halsteadtw\02-235583\100-0009-0209.sht-plan.dgn	DRAWN - TWH	REVISED -	57			D9 BSMART 2011-1	WILLIAMSON	11	10	
PLOT SCALE = 20.0000' / IN.	CHECKED - MAS	REVISED -	CONTRACT NO. 78226							
PLOT DATE = 9/28/2010	DATE - 8/10/10	REVISED -	ILLINOIS FED. AID PROJECT							