



HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT (SY)

MERIDIAN ROAD			
STA	O/S	TYPE	HMA SURF REM BUTT JT (SY)
283+16.79	N/A	MAINLINE	80.0
283+89	Lt	SIDE STREET	85.1
284+29	Rt	SIDE STREET	93.0
285+40	Lt	C.E.	72.5
288+50	Lt	C.E.	44.6
294+05	Lt	C.E.	31.1
300+82	Rt	SIDE STREET	158.9
300+86	Lt	SIDE STREET	141.6
301+98	N/A	MAINLINE	80.0
307+68	N/A	MAINLINE	80.0
308+79	Rt	SIDE STREET	141.6
308+84	Lt	SIDE STREET	158.9
312+49	Lt	C.E.	0.0
313+90	Lt	C.E.	26.9
321+08	Lt	C.E.	32.3
321+10	Rt	SIDE STREET	24.4
332+77	Rt	SIDE STREET	24.4
343+60	Rt	STREET	24.4
350+13	Rt	C.E.	0.0
350+30	Lt	C.E.	0.0
351+20	Rt	C.E.	0.0
352+05.10	N/A	MAINLINE	417.0
352+69.11	N/A	MAINLINE	467.0
363+35	Lt	SIDE STREET	24.4
368+42	Lt	SIDE STREET	24.6
378+01	Rt	F.E.	0.0
379+88	Rt	C.E.	26.4
381+22	Lt	F.E.	0.0
381+75	Rt	P.E.	6.7
382+54	Lt	P.E.	8.6
383+99	Rt	SIDE STREET	22.2
385+17	Lt	P.E.	6.7
386+83	Lt	P.E.	8.9
387+81	Lt	P.E.	0.0
387+91	Rt	SIDE STREET	40.0
388+62	Rt	SIDE STREET	40.0
389+47	Lt	P.E.	6.7
397+04	Rt	SIDE STREET	19.7
415+03	Rt	C.E.	20.0
416+02	Rt	P.E.	0.0
418+85	Rt	P.E.	0.0
420+43	Rt	P.E.	0.0
423+31	Rt	F.E.	0.0
423+48	Lt	F.E.	7.4
425+38	Rt	P.E.	0.0
425+40	Lt	P.E.	6.7
426+31	Rt	P.E.	0.0
431+85	Rt	P.E.	0.0
432+98	Lt	F.E.	0.0
442+41.59	N/A	MAINLINE	109.7
443+75.83	N/A	MAINLINE	111.4
450+63	Lt	F.E.	0.0
452+93	Lt	P.E.	0.0
454+34	Lt	P.E.	0.0
454+68	Rt	P.E.	0.0
458+04	Lt	P.E.	15.8
458+28	Lt	P.E.	0.0
459+54	Rt	P.E.	0.0
461+70	Rt	P.E.	0.0
462+50	Lt	P.E.	15.2
462+79	Rt	P.E.	0.0
462+76	Rt	P.E.	6.7
465+38	Rt	P.E.	6.7
467+73	Rt	P.E.	7.0
469+18	Lt	P.E.	6.8
470+56	Lt	P.E.	0.0
474+13	Rt	C.E.	28.1
476+18	Rt	C.E.	48.2
480+81	Rt	C.E.	21.3
481+92	Lt	P.E.	0.0
482+87	Rt	F.E.	0.0
486+87	Lt	P.E.	6.7
489+85	Rt	SIDE STREET	24.4
490+89	Lt	P.E.	0.0
493+67	Lt	P.E.	0.0
497+86	Lt	P.E.	0.0
499+41	Rt	P.E.	0.0
500+81	Lt	P.E.	6.7
501+40	Rt	P.E.	6.5
504+12	Lt	P.E.	9.2
507+44	Rt	P.E.	6.7
508+19	Rt	P.E.	0.0
510+58	Rt	P.E.	0.0
514+96	Rt	P.E.	0.0
517+29	Lt	F.E.	0.0
528+19	Lt	F.E.	0.0

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT (SY)

MERIDIAN ROAD			
STA	O/S	TYPE	HMA SURF REM BUTT JT (SY)
540+48	Lt	F.E.	0.0
541+30.62	N/A	MAINLINE	80.0
548+50.58	N/A	MAINLINE	80.0
568+31	Rt	SIDE STREET	22.2
575+85	Rt	P.E.	8.9
576+97	Rt	P.E.	160.0
581+19	Rt	P.E.	160.0
581+79	Lt	P.E.	6.7
590+98	Rt	P.E.	8.8
591+26	Rt	P.E.	0.0
591+11	Lt	P.E.	0.0
601+01	Lt	P.E.	0.0
601+95	Lt	P.E.	0.0
604+07	Rt	F.E.	0.0
611+94	Rt	P.E.	0.0
617+18	Rt	P.E.	0.0
620+62	Rt	F.E.	0.0
620+99	Lt	P.E.	6.7
622+60	Lt	P.E.	0.0
623+17	Rt	P.E.	0.0
626+71	Rt	P.E.	0.0
627+49	Lt	P.E.	0.0
631+03	Rt	SIDE STREET	24.4
639+26	Rt	P.E.	0.0
647+60	Rt	SIDE STREET	20.0
123+62	Lt	F.E.	0.0
132+61	Rt	P.E.	0.0
134+05	Rt	P.E.	0.0
146+56	Lt	P.E.	0.0
148+67	Rt	F.E.	0.0
694+80	Rt	F.E.	0.0
698+02	Rt	F.E.	0.0
699+66	Rt	C.E.	0.0
707+89	Rt	F.E.	0.0
711+59	Lt	SIDE STREET	22.7
712+31.71	N/A	MAINLINE	80.0
Sub-Total			3,530.3

TEMPORARY RAMP

MERIDIAN ROAD			
STA	O/S	TYPE	TEMPORARY RAMP (SY)
283+16.79	N/A	MAINLINE	13.3
283+89	Rt	SIDE STREET	13.3
284+29	Rt	SIDE STREET	13.3
300+82	Rt	SIDE STREET	20.3
300+86	Lt	SIDE STREET	17.2
301+98	N/A	MAINLINE	13.3
307+68	N/A	MAINLINE	13.3
308+79	Rt	SIDE STREET	17.2
308+84	Lt	SIDE STREET	20.3
321+10	Rt	SIDE STREET	12.2
332+77	Rt	SIDE STREET	12.2
343+60	Rt	SIDE STREET	12.2
352+05.10	N/A	MAINLINE	138.3
352+69.11	N/A	MAINLINE	145.0
363+35	Lt	SIDE STREET	12.2
368+42	Lt	SIDE STREET	12.2
383+99	Rt	SIDE STREET	11.1
397+04	Rt	SIDE STREET	10.0
436+43	Rt	SIDE STREET	12.2
442+41.63	N/A	MAINLINE	13.3
443+75.87	N/A	MAINLINE	13.3
476+30	Lt	SIDE STREET	12.8
489+85	Rt	SIDE STREET	12.2
541+30.62	N/A	MAINLINE	13.3
548+50.58	N/A	MAINLINE	13.3
568+31	Rt	SIDE STREET	11.1
631+03	Rt	SIDE STREET	12.2
647+60	Rt	SIDE STREET	10.0
139+25	Rt	SIDE STREET	13.3
711+59	Lt	SIDE STREET	13.3
712+31.71	N/A	MAINLINE	13.3
Sub-Total			671.1

TEMPORARY RAMP

STATE STREET			
STA	O/S	TYPE	TEMPORARY RAMP (SY)
83-00	N/A	MAINLINE	55.8
92-85	N/A	MAINLINE	55.8
Sub-Total			111.6
Total			782.7

HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70

MERIDIAN ROAD		
STA	HMA BC IL-19.0 N70 (TON)	
283+16.79 to 301+97.81	793.2	
307+67.81 to 340+86.80	1,399.5	
340+86.80 to 352+05.10	703.4	
352+09.11 to 364+00.41	720.4	
364+00.41 to 392+35.26	1,195.4	
392+35 to 397+49	414.4	
408+90 to 412+99	219.3	
412+99.80 to 429+00.95	673.6	
429+00.95 to 442+41.62	1,023.8	
444+05.83 to 469+50.49	1,073.0	
469+50.49 to 485+00.97	921.8	
485+00.97 to 541+30.62	2,373.8	
548+50.88 to 117+26.02	4,373.0	
117+26.02 to 118+49.55	57.6	
142+00.00 to 150+27.47	493.6	
150+27.46 to 712+31.71	1,142.2	
Sub-Total	17,578.0	

AUBURN ROAD		
STA	HMA BC IL-19.0 N70 (TON)	
89+61 to 93+28	190.6	
104+75 to 110+76	417.3	
Sub-Total	607.9	

DICKENSON ROAD		
STA	HMA BC IL-19.0 N70 (TON)	
13+17.54 to 19+73.52	451.1	
Sub-Total	451.1	

LATHAM ROAD		
STA	HMA BC IL-19.0 N70 (TON)	
1+75.00 to 6+57.91	319.6	
Sub-Total	319.6	
Total	18,956.6	

HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70

MERIDIAN ROAD		
STA	HMA SC "D" N70 (TON)	
283+16.79 to 301+97.81	360.5	
307+67.81 to 340+86.80	636.1	
340+86.80 to 352+05.10	319.7	
352+09.11 to 364+00.41	327.4	
364+00.41 to 392+35.26	543.3	
392+35 to 397+49	188.4	
408+91 to 412+99	99.7	
412+99.80 to 429+00.95	306.2	
429+00.95 to 442+41.62	463.4	
444+05.83 to 469+50.49	487.7	
469+50.49 to 485+00.97	419.0	
548+50.88 to 117+26.02	1,987.7	
117+26.02 to 118+49.55	26.2	
142+00.00 to 150+27.47	224.4	
150+27.47 to 712+31.71	519.2	
Sub-Total	6,911.0	

AUBURN ROAD		
STA	HMA SC "D" N70 (TON)	
89+61 to 93+28	86.6	
104+75 to 110+76	189.7	
Sub-Total	276.3	

DICKENSON ROAD		
STA	HMA SC "D" N70 (TON)	
13+17.54 to 19+73.52	199.8	
Sub-Total	199.8	

HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70

LATHAM ROAD		
STA	HMA SC "D" N70 (TON)	
1+75.00 to 6+57.91	137.9	
Sub-Total	137.9	
Total	7,525.0	

HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50

STATE STREET		
STA	HMA SC "D" N50 (TON)	
83+00 to 92+85	545.8	
Total	545.8	

HOT-MIX ASPHALT PAVEMENT (FULL - DEPTH), 7 1/2"

CEMETERY ROAD		
STA	HMA PAVT FD 7 1/2 (SY)	
194+57.03 to 201+11.19	2,674.3	
201+61.36 to 205+50.43	1,917.7	
Total	4,591.9	

HOT-MIX ASPHALT PAVEMENT (FULL - DEPTH), 9 3/4"

LATHAM ROAD		
STA	HMA PAVT FD 9 3/4 (SY)	
0+24.00 to 1+75.00	1,287.6	
Total	1,287.6	

HOT-MIX ASPHALT PAVEMENT (FULL - DEPTH), 11"

MERIDIAN ROAD		
STA	HMA PAVT FD 11 (SY)	
397+49 to 408+91 (Rt)	2,877.1	
397+49 to 408+91 (Lt)	3,113.3	
118+49.55 to 142+00.00	11,492.2	
Sub-Total	17,482.7	

AUBURN ROAD		
STA	HMA PAVT FD 11 (SY)	
93+28 to 99+55 (Rt)	1,168.3	
93+28 to 99+47 (Lt)	1,268.2	
100+70 to 104+75 (Lt)	807.5	
100+53 to 104+75 (Rt)	964.9	
Sub-Total	4,208.8	
Total	21,691.5	

PORTLAND CEMENT CONCRETE PAVEMENT 9"

MERIDIAN ROAD		
STA	PCC PVT 9 (SY)	
401+72 to 402+67 (Circle)	427.4	
Total	427.4	

COMBINATION CURB AND GUTTER REMOVAL

MERIDIAN ROAD		
STA	O/S	COMB CURB GUTTER REM (FT)
340+86 to 352+07	Lt	1,191.0
348+28 to 351+76	Lt	695.0
353+02 to 356+20	Rt	635.0
351+89 to 352+01 Corner Island	Rt	61.0
352+72 to 352+85 Corner Island	Lt	60.0
352+72 to 352+99 Corner Island	Rt	217.0
352+79 to 354+25	Rt	214.0
414+57.84 to 417+62.09	Lt	321.4
414+57.84 to 417+62.09	Rt	324.4
423+04.34 to 425+85.11	Lt	229.0
456+86.03 to 460+04.54	Rt	200.7
469+85 to 472+00	Lt	215.0
Contingency		200.0
Sub-Total		4,563.5