



Hanson Professional Services Inc.

FILE NAME =
 USER NAME = MWH
 DESIGNED - DPA
 DRAWN - MWH
 CHECKED - DPA
 DATE - 11/04/10
 REVISED -
 REVISED -
 REVISED -
 REVISED -

CONCRETE CURB AND MEDIAN SCHEDULE

LOCATION					60603500	60603800	60605000	60618300	60618800	60624600	X6063600
					COMBINATION CONCRETE CURB AND GUTTER, TYPE B - 6.06	COMBINATION CONCRETE CURB AND GUTTER, TYPE B - 6.12	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	CONCRETE MEDIAN SURFACE, 4 INCH	CONCRETE MEDIAN, TYPE SB	CORRUGATED MEDIAN	COMBINATION CONCRETE CURB AND GUTTER, TYPE M - 4.24
					FOOT	FOOT	FOOT	SQ FT	SQ FT	SQ FT	FOOT
ROADWAY	BEGIN STATION	OFFSET	END STATION	OFFSET							
HARS	313+84.64		CENTER ISLAND		179.0						227.0
	313+46	-49	323+13	-18		1094.0					
	314+19	50	323+13	18		901.0					
	314+42		315+15					702.0			
SUBTOTAL					179.0	1995.0	0.0	0.0	702.0	0.0	227.0
EAST WEST											
	214+83.98		CENTER ISLAND		179.0						227.0
	201+47	-79	213+56	-21		1245.0					
	201+46	55	213+55	13		1220.0					
	213+01		213+68						292.0		
	213+68		214+23					611.0			
	215+41		215+99					590.0			
	215+99	-14	226+54	-18		1055.0			147.0		
	216+02	22	226+54	18		1052.0					
SUBTOTAL					179.0	4572.0	0.0	0.0	1201.0	439.0	227.0
CCDN											
	113+76		CENTER ISLAND		179.0						227.0
	101+39	-86	112+54	-26		1152.0					
	101+53		103+37					755.0			
	103+37	3	112+30	-7		893.0					
	101+38	62	112+63	23		1135.0					
	103+37	7	112+30	7		893.0					
	112+30		112+81					676.0			
	112+81		113+16						486.0		
	114+32		114+67						469.0		
	114+67		115+18					651.0			
	114+84	-22	121+57	-26		672.0					
	115+18	-7	121+57	-7		639.0					
	114+90	26	121+57	26		667.0					
	115+18	7	121+57	7		639.0					
SUBTOTAL					179.0	6690.0	0.0	1327.0	1710.0	0.0	227.0
MAIN CENTRAL											
	1+09	-33	10+18	-30		912.0					
	1+10	-7	10+08	-14		908.0					
	1+17	35	10+16	30		901.0					
	1+10	9	10+08	13		905.0					
	10+08		10+59					996.0			
	10+18	-30	11+28	-113			166.0				
	10+16	30	11+27	114			167.0				
	10+59		10+94						612.0		
	11+77	-122	12+78	-27			161.0				
	11+75	109	12+78	23			158.0				
	12+10		12+45						521.0		
	12+45		12+96					718.0			
	12+78	-27	18+80	-32		605.0					
	12+96	-45	18+70	-16		576.0					
	12+78	23	18+83	29		607.0					
	12+96	8	18+70	13		557.0					
	18+70		19+21					569.0			
	18+88	-32	20+00	-129			186.0				
	18+83	29	19+93	118			173.0				
	19+21		19+55						390.0		
	21+07		21+48					948.0			
	20+35	-128	21+29	-25			164.0				
	20+74		21+07						327.0		
	20+29	115	21+31	25			159.0				
	21+29	-25	22+90	-39		164.0					
	21+48	-9	22+27	-8		79.0					
	21+31	25	22+90	35		163.0					
	21+48	9	22+27	4		79.0					
	22+27		22+80						545.0		
SUBTOTAL					0.0	6456.0	1334.0	3231.0	2395.0	0.0	0.0
IL 38											
	167+23	-29	167+91	-105			116.0				
	168+55	-121	180+49	-54			1253.0				
SUBTOTAL					0.0	0.0	1369.0	0.0	0.0	0.0	0.0
TOTAL					537.0	19713.0	2703.0	4558.0	6008.0	439.0	681.0

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

NORTHERN ILLINOIS UNIVERSITY
FAR WEST CAMPUS EXPANSION
SCHEDULE OF QUANTITIES

F.A.P. RTE. 567	SECTION 06-0002-00-PV	COUNTY DEKALB	TOTAL SHEETS 148	SHEET NO. 6
CONTRACT NO. 87476				

SCALE: AS SHOWN SHEET NO. OF SHEETS STA. TO STA.

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT