



Hanson Professional Services Inc.

LAYOUT: MWH 06/13/10
 DRAWN: MWH 11/04/10
 REVIEWED: DPA 11/04/10
 C:\208\Scrt.dgn

PAVEMENT MARKING SCHEDULE												
LOCATION				78000100	78000200	78000400	78000500	78000600	78000620	78000650	78300100	
				THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	THERMOPLASTIC PAVEMENT MARKING - LINE 18"	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	PAVEMENT MARKING REMOVAL	
BEGIN STATION	OFFSET	END STATION	OFFSET	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	NOTES
Housing Access Road South												
314+42	-9.00	314+32	-34.00							12		WB Circle Edge 18"x2' Dash
314+52	7.00	323+13	0.00		857	Yellow Interior						
314+52	7.00	323+13	0.00		857	Yellow Interior						
314+68		314+76							88			Crosswalk
315+15	0.00	315+72	0.00						20.0			Yellow Median Hatch
SUBTOTAL				0.0	1714.0	0.0	0.0	0.0	20.0	100.0	0.0	0.0
East West Roadway												
201+52	6.00	204+00	5.00		494	Yellow Double					42	EB Stopbar
201+52	-6.00	203+50	-6.00				198	White Turn Line				
201+78	-2.00			62.4	Lt Arrows							
204+00	-6.00	206+00	-5.00		204	Yellow Interior						
204+00	5.00	206+00	5.00		196	Yellow Interior						
204+00	-6.00	206+00	-5.00		50	Yellow Int Dash						
204+00	5.00	206+00	5.00		50	Yellow Int Dash						
206+00	-5.00	210+00	-5.00		795	Yellow Double		136.0	Yellow Median Hatch			
206+00	5.00	210+00	5.00		805	Yellow Double						
210+00	-5.00	212+04	-6.00		203	Yellow Interior						
210+00	5.00	212+04	6.00		206	Yellow Interior						
210+00	-5.00	212+04	-6.00		50	Yellow Int Dash						
210+00	5.00	212+04	6.00		50	Yellow Int Dash						
212+04	-6.00	214+14	-12.00		201	Yellow Interior		88.0	Yellow Median Hatch			
212+04	6.00	214+13	2.00		203	Yellow Interior						
213+88		213+96							80			Crosswalk
214+23	4.00	214+31	31.00						12			EB Circle Edge 18"x2' Dash
215+41	-4.00	215+35	-27.00						10			WB Circle Edge 18"x2' Dash
215+51	-2.00	226+54	0.00		1096	Yellow Interior		46.0	Yellow Median Hatch			
215+50	12.00	226+54	0.00		1095	Yellow Interior						
215+68		215+76							80			Crosswalk
SUBTOTAL				62.4	5698	0.0	198.0	270.0	182.3	42.0	0.0	0.0
Convocation Center Drive North												
101+80	-4.00			46.8	Lt Arrows							
101+55	-8.00	102+94	-8.00				139	White Turn Line			40	EB Stopbar
112+30	-9.00	113+05	-12.00		68	Yellow Interior						
112+30	8.00	113+04	5.00		67	Yellow Interior						
112+80		112+88							88			Crosswalk
113+15	8.00	113+23	33.00						12			EB Circle Edge 18"x2' Dash
114+33	-7.00	114+21	-40.00						15			WB Circle Edge 18"x2' Dash
114+43	-4.00	115+18	-8.00		67	Yellow Interior						
114+42	12.00	115+18	8.00		68	Yellow Interior						
114+59		114+67										
SUBTOTAL				46.8	270.0	0.0	139.0	0.0	211.4	96.0	40.0	0.0
Main Central Roadway												
0+62	-46.00	10+58	-26.00		1003	White Edge						
0+53	46.00	10+58	23.00		1010	White Edge						
0+38	-3.00	10+75	-9.00		1038	Yellow Inside						
0+38	4.00	10+75	9.00		1038	Yellow Inside						
0+57	-9.00	0+67	-42.00							27		Stopbar
0+75	-20.00	1+81	-25.00				106	White Lane Line				
1+81	-25.00	7+33	-37.00									
0+82	22.00	7+29	37.00				140	White CenterDash				
0+47	9.00	0+47	50.00				170	White CenterDash				
0+53	10.00	0+53	47.00				41	White Crosswalk	72.0			White NB Crosswalk
0+47	-7.00	0+58	-50.00				37	White Crosswalk				
0+53	-9.00	0+62	-46.00				42	White Crosswalk	82.0			White SB Crosswalk
11+13	0.00	11+90	0.00				39	White Crosswalk				
10+58		10+66			242	Yellow Round						
10+66	-27.00	11+32	-88.00		96	White Edge				88		Crosswalk
10+66	24.00	11+26	84.00		90	White Edge						
10+93	-12.00	10+95	14.00				48	White Radius w/ Leg				
10+95	14.00	11+05	43.00							13.7		NB Circle Edge 18"x2' Dash
11+37	56.00	11+60	57.00				45	White Radius w/ Leg				
11+44	-61.00	11+67	-60.00				45	White Radius w/ Leg				
11+79	-88.00	12+37	-25.00		95	White Edge						
11+71	84.00	12+37	23.00		90	White Edge						
11+99	-49.00	12+10	-16.00							14		SB Circle Edge 18"x2' Dash
12+10	-16.00	12+11	8.00				42	White Radius w/ Leg				
12+37		12+45								88		Crosswalk

CONTINUED

FILE NAME = C:\208\Scrt.dgn	USER NAME = MWH	DESIGNED - DPA	REVISIONS -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	NORTHERN ILLINOIS UNIVERSITY FAR WEST CAMPUS EXPANSION SCHEDULE OF QUANTITIES	F.A.P. RTE. 567	SECTION 06-00002-00-PV	COUNTY DEKALB	TOTAL SHEETS 148	SHEET NO. 7	CONTRACT NO. 87476
PLOT SCALE = AS SHOWN	CHECKED - DPA	REVISIONS -	SCALE: AS SHOWN			SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
PLOT DATE = 11/05/2010	DATE 11/04/10	REVISIONS -									